

AD-A109 974

FLAHERTY-GIAVARA ASSOCIATES NEW HAVEN CT
NATIONAL DAM SAFETY PROGRAM, GUILFORD LAKE DAM (INVENTORY NUMBRE--ETC(U)
SEP 81 H C FLAHERTY


F/B 13/13


DACW51-81-C-0006

NL

UNCLASSIFIED

1 of 2
pages





MICROCOPY RESOLUTION TEST CHART
NATIONAL BUREAU OF STANDARDS-1963-A

REPORT DOCUMENTATION PAGE

READ INSTRUCTIONS
BEFORE COMPLETING FORM

1. REPORT NUMBER	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
AD-A109974		
4. TITLE (and Subtitle) Phase I Inspection Report Guilford Lake Dam Susquehanna River Basin, Chenango County, New York Inventory No. 1483		5. TYPE OF REPORT & PERIOD COVERED Phase I Inspection Report National Dam Safety Program
7. AUTHOR(s) HUGH C. FLAHERTY		6. PERFORMING ORG. REPORT NUMBER
9. PERFORMING ORGANIZATION NAME AND ADDRESS Flaherty-Giavara Associates One Columbus Plaza New Haven, CT 06510		8. CONTRACT OR GRANT NUMBER(s) DACW51-81-C-0006
11. CONTROLLING OFFICE NAME AND ADDRESS Department of the Army 26 Federal Plaza New York District, CofE New York, New York 10287		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office) Department of the Army 26 Federal Plaza New York District, CofE New York, NY 10287		12. REPORT DATE 15 September 1981
15. DISTRIBUTION STATEMENT (of this Report) Approved for public release; Distribution unlimited.		13. NUMBER OF PAGES
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 2), if different from Report)		15. SECURITY CLASS. (of this report) UNCLASSIFIED
19. SUPPLEMENTARY NOTES Original contains color plates: All DTIC reproductions will be in black and white.		16. DECLASSIFICATION/DOWNGRADING SCHEDULE
18. KEY WORDS (Continue on reverse side if necessary and identify by block number) Dam Safety National Dam Safety Program Visual Inspection Hydrology, Structural Stability		Guilford Lake Dam Chenango County Susquehanna River Basin
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) This report provides information and analysis on the physical condition of the dam as of the report date. Information and analysis are based on visual inspection of the dam by the performing organization. Examination of available documents and visual inspections of the dam did not reveal conditions which constitute an immediate hazard to human life or property. However, the dam has some deficiencies that need to be evaluated and remedied.		

LEVEL

DTIC
SELECTED

JAN 25 1982

H

DTIC FILE COPY

DD FORM 1 JAN 73 1-73 (EDITION OF 1 NOV 65 IS OBSOLETE)

01 15 82 065

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

412 399

AD A109974

Using the Corps of Engineers' screening criteria for the initial review of spillway adequacy, it has been determined that the dam would be overtopped by all storms exceeding 16 percent of the Probable Maximum Flood (PMF). Dam overtopping, the resulting erosion of the embankment and hence, dam breaching would cause water surface levels downstream to reach depths which would pose significant danger to residents. Therefore, the spillway is adjudged to be seriously inadequate and the dam is assessed as unsafe, non-emergency.

The classification "unsafe" applied to a dam because of a seriously inadequate spillway is not meant to connote the same degree of emergency as would be associated with an "unsafe" classification applied for a structural deficiency. It does mean that there appears to be a serious deficiency in spillway capacity and if a severe storm were to occur, overtopping and failure of the dam could take place, significantly increasing the hazard to life downstream of the dam.

DISCLAIMER NOTICE

**THIS DOCUMENT IS BEST QUALITY
PRACTICABLE. THE COPY FURNISHED
TO DTIC CONTAINED A SIGNIFICANT
NUMBER OF PAGES WHICH DO NOT
REPRODUCE LEGIBLY.**

¹ SUSQUEHANNA RIVER BASIN

² **GUILFORD LAKE DAM**

CHENANGO COUNTY, NEW YORK
INVENTORY No. NY 1483

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM



APPROVED FOR PUBLIC RELEASE;
DISTRIBUTION UNLIMITED

NEW YORK DISTRICT, CORPS OF ENGINEERS
JUNE 1981

01 13 62 085

PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I Investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through frequent inspections can unsafe conditions be detected and only through continued care and maintenance can these conditions be prevented or corrected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the Spillway Test Flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. Because of the magnitude and rarity of such a storm event, a finding that a spillway will not pass the test flood should not be interpreted as necessarily posing a highly inadequate condition. The test flood provides a measure of relative spillway capacity and serves as an aid in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.



Approved for	
Reviewed by	
Justification	
Unreliable	
Approved	
Distribution	
By	
Code	234

I

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM
GUILFORD LAKE DAM
INVENTORY NO. NY 1483
SUSQUEHANNA RIVER BASIN
CHENANGO COUNTY, NEW YORK

TABLE OF CONTENTS

	<u>PAGE NO.</u>
ASSESSMENT	-
OVERVIEW PHOTOGRAPH	-
LOCATION MAP	1
1 - PROJECT INFORMATION	1
1.1 GENERAL	1
1.2 DESCRIPTION OF PROJECT	1
1.3 PERTINENT DATA	3
2 - ENGINEERING DATA	5
2.1 GEOTECHNICAL DATA	5
2.2 DESIGN RECORDS	5
2.3 CONSTRUCTION RECORDS	6
2.4 OPERATION RECORDS	6
2.5 EVALUATION OF DATA	6
3 - VISUAL INSPECTION	7
3.1 FINDINGS	7
3.2 EVALUATION OF OBSERVATIONS	8
4 - OPERATION AND MAINTENANCE PROCEDURES	9
4.1 PROCEDURE	9
4.2 MAINTENANCE OF DAM	9
4.3 WARNING SYSTEM	9
4.4 EVALUATION	9

1

C

5 - HYDROLOGIC/HYDRAULIC	10
5.1 DRAINAGE AREA CHARACTERISTICS	10
5.2 ANALYSIS CRITERIA	10
5.3 SPILLWAY CAPACITY	10
5.4 RESERVOIR CAPACITY	11
5.5 FLOODS OF RECORD	11
5.6 OVERTOPPING POTENTIAL	11
5.7 EVALUATION	12
6 - STRUCTURAL STABILITY	13
6.1 EVALUATION OF STRUCTURAL STABILITY	13
6.2 STRUCTURAL STABILITY ANALYSIS	13
7 - ASSESSMENT/RECOMMENDATIONS	16
7.1 ASSESSMENT	16
7.2 RECOMMENDED MEASURES	17

APPENDICES

- A. PHOTOGRAPHS
- B. VISUAL INSPECTION CHECKLIST
- C. HYDROLOGIC/HYDRAULIC ENGINEERING DATA AND COMPUTATIONS
- D. PREVIOUS INSPECTION REPORTS/AVAILABLE DOCUMENTS
- E. STRUCTURAL STABILITY ANALYSIS
- F. REFERENCES
- G. DRAWINGS

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM

Name of Dam: Guilford Lake Dam
State Located: New York
County: Chenango
Watershed: Susquehanna River Basin
Watercourse: Guilford Creek
Dates of Inspection: March 12 and 14, 1981

ASSESSMENT

Examination of available documents and visual inspections of the dam did not reveal conditions which constitute an immediate hazard to human life or property. However, the dam has some deficiencies that need to be evaluated and remedied.

Using the Corps of Engineers' screening criteria for the initial review of spillway adequacy, it has been determined that the dam would be overtopped by all storms exceeding 16 percent of the Probable Maximum Flood (PMF). Dam overtopping, the resulting erosion of the embankment and hence, dam breaching would cause water surface levels downstream to reach depths which would pose significant danger to residents. Therefore, the spillway is adjudged to be seriously inadequate and the dam is assessed as unsafe, non-emergency.

The classification "unsafe" applied to a dam because of a seriously inadequate spillway is not meant to connote the same degree of emergency as would be associated with an "unsafe" classification applied for a structural deficiency. It does mean that there appears to be a serious deficiency in spillway capacity and if a severe storm were to occur, overtopping and failure of the dam could take place, significantly increasing the hazard to life downstream of the dam.

It is recommended that the following additional investigations be performed by a registered professional engineer engaged by the owner:

1. Conduct a detailed hydrologic and hydraulic analysis to more accurately determine the site specific characteristics of the watershed.

2. No design or construction data was available; therefore, attempt to obtain plans or details of the structure including the construction history and the nature and properties of the foundation bearing materials as well as the materials behind the spillway. This data is necessary to implement Investigations 3 and 4 below. If no such data is available, it may be necessary to conduct subsurface explorations to obtain the information required for the appropriate assessments.
3. Perform a structural stability analysis on the dam using data obtained as a result of Investigation 2 that will assess the effect of the earth and rockfill behind the spillway on the overall stability of the spillway and recommend remedial measures, if necessary.
4. The concrete spillway apron was severely cracked and deteriorated; therefore, design a new concrete or riprap apron for the spillway and recommend an appropriate method to construct it.

It is recommended that within 3 months of the final approval date of this report, all of the additional investigations should be initiated and within 18 months, appropriate remedial measures should be completed. In the interim, a plan for providing around-the-clock surveillance of the dam during periods of unusually heavy precipitation should be developed and implemented.

The following remedial measures should be completed within 12 months to correct existing deficiencies:

1. Remove the fallen logs in the discharge channel and clear the brush and trees from the side slopes.
2. Repair the cracked 6 inch diameter gate valve on the water distribution pipe (reservoir drain).




PHOTO #1: Overview of Guilford Lake Dam
Inventory No. NY 1483

3. Develop and implement a flood warning and emergency evacuation plan to alert downstream residents in the event conditions occur which could result in failure of the dam.


Submitted by:

FLAHERTY GIAVARA ASSOCIATES, P.C.



Hugh C. Flaherty, P.E. & L.S.
Chairman of the Board
New York License No. 58508


Approved by:



Col. W. M. Smith, Jr.
New York District Engineer

Date:

15 Sep 81



LOCATION MAP

GUILFORD LAKE DAM
INVENTORY No. NY 1483

SUSQUEHANNA RIVER BASIN
CHENANGO COUNTY
GUILFORD, NEW YORK

FLAHERTY • GIAVARA ASSOCIATES, P.C.

NATIONAL DAM SAFETY PROGRAM
PHASE I INSPECTION REPORT
GUILFORD LAKE DAM
INVENTORY NO. 1483
D.E.C. NO. 118A-4464
SUSQUEHANNA RIVER BASIN
CHENANGO COUNTY, NEW YORK

SECTION 1 - PROJECT INFORMATION

1.1 GENERAL

a. Authority

The Phase I Inspection reported herein was authorized by the Department of the Army, New York District, Corps of Engineers, to fulfill the requirements of the National Dam Inspection Act, Public Law 92-367. Flaherty Giavara Associates, P.C. has been retained by the New York District to inspect and report on selected dams in the State of New York. Authorization and notice to proceed was issued to Flaherty Giavara Associates, P.C. under a letter of December 24, 1980 from W. M. Smith Jr., Colonel, Corps of Engineers. Contract No. DACW 51-81-C-0006 has been assigned by the Corps of Engineers for this work.

b. Purpose

Evaluation of the existing conditions of the subject dam to identify deficiencies and hazardous conditions, determine if they constitute hazards to life and property and recommend remedial measures where necessary.

1.2 DESCRIPTION OF PROJECT

a. Description of Dam and Appurtenances

Guilford Lake Dam is an earth and rockfill structure consisting of an overflow spillway spanning the majority of the length of the dam. The spillway weir and downstream face have been capped with concrete and concrete abutments and retaining walls exist at either end of the spillway. The concrete portions of the dam were refurbished in 1978 and 1979.

The overall length of the dam is 62 feet and the height is 15 feet. Other pertinent data on the dam is included in Section 1.3. A cast iron water supply pipe extends through the dam near the bottom of the spillway in proximity to the right abutment.

The discharge channel is rock-lined and 15+ feet wide. The channel side slopes are approximately 1.5 horizontal to 1 vertical. The left side slope is predominantly a rock cut, while the right side slope appears to be an earth cut with occasional rock outcrops.

b. Location

The Guilford Lake Dam is located off Chenango County Road 35 approximately 0.4 miles west of the village of Guilford in the Town of Guilford, New York. The dam is located at latitude north 42°-24.6' and longitude west 75°-29.8' on the U.S. Geological Survey 7.5 minute series topographic map "Guilford, New York". The Location Map on page 1 indicates where the dam is situated.

c. Size Classification

The maximum height of the dam is 15 feet and the maximum storage capacity is 560 acre-feet. Therefore, Guilford Lake Dam is classified as a "Small" dam as defined by the Recommended Guidelines for Safety Inspection of Dams.

d. Hazard Classification

There are two roads and approximately 10 buildings within the dam failure flood hazard area. Therefore, the dam is in the "High" hazard category as defined by the Recommended Guidelines for Safety Inspection of Dams.

e. Ownership

The dam is owned by the Town of Guilford. The address and telephone number is as follows:

Owner

Contact: Mr. Austin Bourn
Highway Superintendent
Town of Guilford
R.D. 1 - Box 103
Guilford, New York 13780

Telephone: (607) 895-6818

f. Purpose

The primary purpose of this dam is water supply for the Town of Guilford.

g. Design and Construction History

An accurate date of construction is unknown; however, the dam has been described in deeds dating back to 1827. The construction history of the dam indicates that it was breached in the late nineteenth century and subsequently was reconstructed. The only major post construction modification noted was the concrete refurbishing of the spillway done in 1978 and 1979 by the County of Chenango.

h. Normal Operating Procedure

There are no regular operating procedures for this dam. The normal water level in the reservoir is maintained by the crest elevation of the spillway weir at approximately 1558.0 (NGVD).

1.3 PERTINENT DATA

a. <u>Drainage Area (Square Miles)</u>	2.23
b. <u>Discharge at Dam Site (CFS)</u>	
- Top of Dam	451
- Crest of Spillway	3
- Reservoir Drain Inlet	-
c. <u>Elevations (NGVD - estimated)</u>	
- Top of Dam	1560.2
- Crest of Spillway	1558.0
- Reservoir Drain Inlet	-
d. <u>Reservoir Surface Area (Acres)</u>	
- Top of Dam	84
- Crest of Spillway	74
- Reservoir Drain Inlet	-
e. <u>Storage (Acre-Feet)</u>	
- Top of Dam	560
- Crest of Spillway	390
- Reservoir Drain Inlet	-
f. <u>Dam</u>	
- Type: Earth and rockfill	
- Length (Feet)	62
- Upstream Slope (H:V)	-
- Downstream Slope (H:V)	1:9
- Crest Width (Feet)	8.3

g. Spillway

- Type: Concrete weir, abutments, downstream face and apron
- Length (Feet) 43.5
- Width (Feet) 8.3
- Side Slopes (H:V) vertical
- Control: None

h. Spillway Discharge Channel

- Type: Excavated into earth
- Length (Feet) 50+
- Bottom Width (Feet) 15+
- Side Slopes (H:V) 1.5:1
- Channel Bottom Slope (Feet/Foot) -
- Control: None

i. Reservoir Drain

- Type: 6 inch diameter cast iron water supply distribution main also serves as the reservoir drain
- Control: Two 6 inch gate valves

SECTION 2 - ENGINEERING DATA

2.1 GEOTECHNICAL DATA

a. Geology

The Guilford Lake Dam is located on Guilford Creek, a southeasterly flowing tributary to the Unadilla River, about 0.4 miles northwest of the village of Guilford in the Allegheny Plateau physiographic province of New York State.

The topography in the area ranges from elevation 1540 in the streambed downstream of the dam to elevation 1700 atop the hills immediately north and south of the dam. The elevation of Guilford Lake behind the dam is 1558 (NGVD).

Exposed bedrock at the site is the Oneonta Formation, belonging to the Upper Devonian Genesee group. This formation consists of red to green and reddish brown, medium-bedded sandstones and coarse silty sandstones, with minor amounts of conglomerate. It is well-jointed locally and contains numerous current features such as cross-bedding and ripple marks. This formation represents a terrestrial deposit (at or just above sea level) containing a mosaic of distributary channel, floodplain and beach deposits, and is part of the massive Catskill Delta complex that prograded across the state from east to west.

Where bedrock is not exposed, some or all of the valley bottom may be mantled with glacial till, a heterogeneous mixture of clay, silt, sand, gravel and cobbles, deposited at the base of ice sheets that once covered the region. This in turn is probably overlain by well-sorted sands and gravels deposited first by glacial meltwater streams and later by Guilford Creek and subsidiary tributary streams.

b. Subsurface Conditions

There are no known records of subsurface explorations at the site of Guilford Lake Dam.

2.2 DESIGN RECORDS

No records were obtained concerning the original design of the dam.

2.3 CONSTRUCTION RECORDS

The dam is known to have existed in some form as far back as 1827, but no construction records were available.

2.4 OPERATION RECORDS

No operation records were obtained for this dam.

2.5 EVALUATION OF DATA

The data presented herein was obtained primarily from the files of the New York State Department of Environmental Conservation (DEC) but also from the Town of Guilford. This information appears to be reliable and adequate for the purposes of a Phase I Inspection Report.

SECTION 3 - VISUAL INSPECTION

3.1 FINDINGS

a. General

Visual inspections of the Guilford Lake Dam were conducted on March 12 and 14, 1981. The weather was mostly overcast and the temperature was 35+°F. At the time of the inspection, there were patches of snow on the ground and water was flowing over the spillway (See Photo No. 5).

b. Dam

The embankment portion of this dam is generally in good condition (See Photo No. 1). There was no visible evidence of lateral movement, settlement, erosion or other serious defects.

c. Spillway

The spillway is generally in good condition (See Photos No. 4, 5, 6, 7, 8, 9, and 10); and except for the apron, there was no visible evidence of lateral movement, settlement or cracking and no seepage was observed at or behind the abutment walls.

The following specific items were noted:

1. The concrete spillway apron was severely cracked and deteriorated, and major portions of it were displaced or eroded away (See Photo No. 11).
2. Earth and rockfill were observed to extend approximately 20 feet back from the spillway before sloping down into the reservoir. The top of this fill was 10 to 15 inches below the top of the spillway. The water level behind the spillway on the date of the visual examination was approximately level with the top of the spillway (See Photo No. 3).
3. A few small diameter fallen logs were observed in the discharge channel and the side slopes of the discharge channel were covered with trees and brush (See Photo No. 12) and several logs and other debris have accumulated on them. Neither the material in the channel bottom nor the material on the side slopes represents a potential threat to blockage of flow in the discharge channel.
4. A 6 inch diameter gate valve on the cast iron water distribution pipe was cracked and leaking (See Photo

No. 13).

d. Downstream Channel

The natural channel downstream of the dam is located beyond the spillway. It has a width of 15+ feet and a depth of 6 inches (See Photo No. 12).

e. Reservoir - Storage Pool Area

The reservoir area is bordered by Chenango County Road 35 on the south edge of the impoundment and moderately sloping open fields and woodlands to the north, east and west (See Photo No. 2). There does not appear to be any significant probability of landslides into the storage pool affecting the safety of the dam.

3.2 EVALUATION OF OBSERVATIONS

Visual inspections revealed some deficiencies on this structure. The following items were noted:

- a. The concrete spillway apron was severely cracked and deteriorated.
- b. Earth and rockfill were observed to extend 20+ feet behind the dam before sloping down to the reservoir.
- c. A few small diameter fallen logs were noted in the spillway discharge channel and its side slopes were covered with trees and brush.
- d. A 6 inch gate valve on the water distribution pipe (reservoir drain) was cracked and leaking.

SECTION 4 - OPERATION AND MAINTENANCE PROCEDURES

4.1 PROCEDURES

The normal water surface level is maintained by the crest of the spillway weir at elevation 1558.0 (NGVD). The only operational procedure in effect at this time is the withdrawal of water through the 6 inch diameter cast iron pipe for water supply to the Town of Guilford.

4.2 MAINTENANCE OF DAM

No regular maintenance operations are performed on Guilford Lake Dam.

4.3 WARNING SYSTEM

No warning system is presently in effect.

4.4 EVALUATION

Presently, there are no maintenance procedures in effect for this dam. Therefore, a program for regular maintenance should be developed and implemented.

SECTION 5 - HYDROLOGIC/HYDRAULIC

5.1 DRAINAGE AREA CHARACTERISTICS

The dam is located in the Town of Guilford on Guilford Creek, approximately 7.5 miles upstream of the Unadilla River. Guilford Creek joins the Unadilla River at the village of East Guilford, 1.5+ miles upstream of the Susquehanna River at Sidney, New York.

The watershed (shown on the Watershed Map on Page C-5 in Appendix C) consists of 1,430 acres (2.23 square miles) of rolling uplands with typical slopes of 5 percent. Land within the watershed is primarily agricultural with extensive open fields. There are no significant waterbodies within the drainage area; however, there are three wetland areas of 15, 3 and 9 acres approximately 5000 feet, 7000 feet and 9000 feet respectively, upstream from the dam.

The watercourse upon which the reservoir is located, is a perennial stream with a typical flow width of 15 feet and a typical flow depth of 6 inches.

5.2 ANALYSIS CRITERIA

The purpose of the hydrologic/hydraulic analysis is to evaluate the spillway capacity and the potential for overtopping. The analysis of the spillway capacity of the dam and storage of the reservoir was performed using the Corps of Engineers' HEC-1 Computer Model - Dam Safety Version. The procedure included determining the Probable Maximum Flood (PMF) runoff from the watershed and routing the inflow hydrograph through the impoundment to determine the outflow hydrograph. The unit hydrograph was defined by the Snyder Synthetic Unit Hydrograph method, and the Modified Puls routing procedure was incorporated.

The initial rainfall loss was assumed to be 1.0 inches, and the uniform rainfall loss was assumed to be 0.1 inches per hour. In accordance with recommended guidelines of the Corps of Engineers, the Probable Maximum Precipitation (PMP) was 20.3 inches (24 hour duration, 200 square mile area).

The analysis was conducted for both the full PMF and for several fractional PMF conditions. The PMF inflow of 4,833 CFS was routed through the reservoir and the peak outflow was determined to be 3,852 CFS.

5.3 SPILLWAY CAPACITY

The total outlet capacity is the sum of the discharges from the spillway and the water distribution pipe. However, for the purpose of this analysis and to be conservative, it was

assumed the gate valves on the reservoir drain were in the closed position.

The spillway consists of a 45 foot long broad-crested concrete weir.

The stage discharge data for the spillway was calculated for the stages tabulated below:

<u>Stage (Feet)</u>	<u>Discharge Capacity (CFS)</u>	<u>Element of Structure</u>
1558.0	0	Spillway Crest
1558.5	48	--
1559.0	135	--
1559.5	248	--
1559.8	326	Top of Left Abutment
1560.0	385	--
1560.2	451	Top of Dam

The total spillway capacity at the top of dam is 451 CFS.

5.4 RESERVOIR CAPACITY

The storage capacity of the reservoir was calculated for the stages indicated below:

<u>Stage (Feet)</u>	<u>Storage (Acre-Feet)</u>	<u>Storage (Inches of Runoff)</u>
1558.0	390	3.27
1560.2	560	4.70

5.5 FLOODS OF RECORD

No data regarding flood levels was obtained for this dam; however, the dam was washed out in the late nineteenth century.

5.6 OVERTOPPING POTENTIAL

The results of the HEC-1 DB computer analysis indicate that the crest of the dam is overtopped by all storms exceeding 16 percent of the PMF event. The PMF discharge rate of 3,852 cubic feet per second (CFS) would occur at a peak flood stage of 1565.7 feet, which is 5.5 feet above the crest of the dam.

The results of the analysis are on the following page:

<u>Flood Condition</u>	<u>Peak Inflow (CFS)</u>	<u>Peak Outflow (CFS)</u>	<u>Maximum Stage Elevation (NGVD)</u>
0.5 PMF	2416	1860	1562.8
1.0 PMF	4833	3852	1565.7

5.7 EVALUATION

Using the Corps of Engineers' screening criteria for the initial review of spillway adequacy, it has been determined that the capacity of the spillway is not adequate to pass one half the PMF; only approximately 16 percent of the PMF can be safely passed before overtopping will occur (assuming the worst condition; i.e., the valves of the principal spillway are closed). The PMF event would overtop the dam for a duration of 15 hours and the maximum depth of flow over the crest would be 5.5 feet. It is estimated that breaching of the dam as a result of overtopping, would cause water surface levels downstream to reach depths which would pose significant danger to residents. Therefore, the spillway is adjudged to be seriously inadequate and the dam is assessed as unsafe, non-emergency.

SECTION 6 - STRUCTURAL STABILITY

6.1 EVALUATION OF STRUCTURAL STABILITY

a. Visual Observations

Except for the deteriorated concrete apron, there was no visible evidence of settlement, lateral movement or other signs of overall structural instability of the dam during the site examination. Based on the conditions that were observed, there would be no reason to question the static structural stability of the dam. However, lateral forces associated with the fill behind the spillway should be considered in any overall evaluation of dam stability.

b. Design and Construction Data

There is no construction data to confirm the actual nature and physical properties of foundation bearing materials which are expected to be bedrock. However, the apparent satisfactory performance of the dam indicates that there is some safety margin with respect to stability under static loading conditions, even with the earth and rockfill behind the dam.

c. Operating Records

No operating records were obtained for Guilford Lake Dam.

d. Post Construction Changes

The only post construction change noted was the concrete refurbishing of the spillway in 1978 and 1979.

6.2 STRUCTURAL STABILITY ANALYSIS

Available information and field data indicate this spillway is a consolidated rock section with a thin concrete cap and downstream face protective slab. Due to the lack of continuity of the cross section, no resistance to overturning could be assessed for this structure. In addition, the theoretical location of the resultant of forces does not apply to a structure of noncontinuous material. As part of the present study, stability computations relative to the sliding factors of safety were performed.

The stability analysis is presented in Appendix E. The results of the stability computations are summarized in the table on the following page:

Loading Condition (Spillway Section)	¹ Factors of Safety		³ Location of Resultant Passing Through Base
	Over- turning	² Sliding	
1. Normal loading condition: water level at 1 foot above spillway crest	N/A	1.86	N/A
2. Maximum operating condition: water level at top of dam (4.2 feet above spillway crest)	N/A	1.62	N/A
3. 0.5 PMF condition: water level at El. 1562.8 (4.8 feet above spillway crest)	N/A	1.26	N/A
4. Ice loading condition: 5.0 Kips per foot acting at top of spillway	N/A	1.15	N/A

¹These factors of safety indicate the ratio of forces resisting sliding to those causing sliding.

²As determined applying the friction-shear method.

³As a result of the type of material comprising the spillway core this number cannot be determined.

The analysis indicates that the consolidation of the earth and rockfill capped with concrete and the consolidated material which has accumulated behind the spillway contribute significantly to the stability of the structure.

Nonetheless for all cases of loading, the factors of safety against sliding were marginal to unacceptable.

The fact that the spillway exhibits apparently good structural stability can be explained by the indeterminate nature of the material accumulating behind it.

The Guilford Lake Dam is located in Seismic Zone I and in accordance with recommended Phase I guidelines does not require seismic analysis.

SECTION 7 - ASSESSMENT/RECOMMENDATIONS

7.1 ASSESSMENT

a. Condition

On the basis of the visual examination, the Guilford Lake Dam is considered to be in good condition. There were no signs of overall impending structural failure, but a concern exists relative to the condition of the apron, which may warrant prompt remedial action to prevent continued erosion which may lead to undermining of the spillway.

b. Adequacy of Information

The evaluation of this dam is based primarily on visual examination, approximate hydraulic and hydrologic computations, and application of engineering judgement. No information was available on the bearing materials on which the dam was built. However, the available information that was obtained is adequate for the purposes of a Phase I assessment.

c. Need for Additional Investigations

It is recommended that the following additional investigations be performed by a registered professional engineer engaged by the owner:

1. Conduct a detailed hydrologic and hydraulic analysis to more accurately determine the site specific characteristics of the watershed.
2. No design or construction data was available; therefore, attempt to obtain plans or details of the structure including the construction history and the nature and properties of foundation bearing materials as well as the materials behind the spillway. This data is necessary to implement Investigations 3 and 4 below. If no such data is available, it may be necessary to conduct subsurface explorations to obtain the information required for the appropriate assessments.
3. Perform a structural stability analysis on the dam using data obtained as a result of Investigation 2 that will assess the effect of the earth and rockfill behind the spillway on the overall stability of the spillway and recommend remedial measures, if necessary.
4. The concrete spillway apron was severely cracked and deteriorated; therefore, design a new concrete or

riprap apron for the spillway, and recommend an appropriate method to construct it.

d. Urgency


It is recommended that within 3 months of the final approval date of this report, all of the additional investigations should be initiated and within 18 months, appropriate remedial measures should be completed. In the interim, a plan for providing around-the-clock surveillance of the dam during periods of unusually heavy precipitation should be developed and implemented. The recommended corrective measures listed in Section 7.2 should be accomplished within 12 months of final approval.

7.2 RECOMMENDED MEASURES

It is considered important that the following items be accomplished in addition to any items required as a result of the additional investigations recommended in Section 7.1c:

- a. Remove the fallen logs in the discharge channel and clear the brush and trees from the side slopes.
- b. Repair the cracked 6 inch diameter gate valve on the water distribution pipe (reservoir drain).
- c. Develop and implement a flood warning and emergency evacuation plan to alert downstream residents in the event conditions occur which could result in failure of the dam.

APPENDIX A
PHOTOGRAPHS



LEGEND

Number refers to caption.
 Arrow indicates direction
 of photograph.

PHOTO LOCATION MAP

GUILFORD LAKE DAM
 INVENTORY No. NY 1483
 CHENANGO COUNTY
 GUILFORD, NEW YORK



PHOTO #2: Overview of impoundment



PHOTO #3: Crest of dam looking toward right abutment




PHOTO #4: Overview of upstream face of dam



PHOTO #5: Overview of downstream face of dam



PHOTO #6: Upstream face of dam




PHOTO #7: Downstream face of dam



PHOTO #8: Close-up of downstream face of dam
at right abutment




PHOTO #9: Close-up of downstream face at center
of dam



PHOTO #10: Close-up of downstream face of dam
at left abutment




PHOTO #11: Concrete apron (broken up) at
downstream face of spillway



PHOTO #12: Downstream channel conditions




PHOTO #13: Water system appurtenances (6 inch diameter water main and two six inch water valves - one with a split casing)

APPENDIX B

VISUAL INSPECTION CHECKLIST

VISUAL INSPECTION CHECKLIST

1) Basic Data

a. General

Name of Dam Guilford Lake Dam
Fed. I.D. # NY 1483 DEC Dam No. 118A-4464
River Basin Susquehanna
Location: Town Guilford County Chenango
Stream Name Guilford Creek
Tributary of Unadilla River
Latitude (N) 42° - 24.6' Longitude (W) 75° - 29.8'
Type of Dam Stone and concrete gravity
Hazard Category High
Date(s) of Inspection March 12 and 14, 1981
Weather Conditions Overcast, 35° ± F.
Reservoir Level at Time of Inspection Elevation 1558.1 ± (NGVD)

b. Inspection Personnel R.C. Smith, T.L. Ward & R.A. Criscuolo of Flaherty Giavara Associates, P.C.; P.L. LeCount & J.J. Rixner of Haley & Aldrich, Inc.; E. Thomas of Salmon Associates

c. Persons Contacted (Including Address & Phone No.)
Clifford E. Wade, Supervisor
Town of Guilford
R.D. 1 - Box 103
Guilford, New York 13780

d. History:

Date Constructed Prior to 1827 Date(s) Reconstructed 1978-1979

Designer Unknown

Constructed By Unknown

Owner Town of Guilford

2) Embankment

a. Characteristics

- (1) Embankment Material Unknown
- (2) Cutoff Type Unknown
- (3) Impervious Core Unknown
- (4) Internal Drainage System None observed
- (5) Miscellaneous No comments

b. Crest

- (1) Vertical Alignment Good; no cracks observed
- (2) Horizontal Alignment Good; both the left and right sections of the spillway angle toward the center section
- (3) Surface Cracks None observed
- (4) Miscellaneous The spillway was recently (1978-1979) refaced

c. Upstream Slope

- (1) Slope (Estimate - V:H) Unknown
- (2) Undesirable Growth or Debris, Animal Burrows None observed
- (3) Sloughing, Subsidence or Depressions None apparent

(4) Slope Protection Not applicable

(5) Surface Cracks or Movement at Toe None evident

d. Downstream Slope

(1) Slope (Estimate - V:H) 9:1

(2) Undesirable Growth or Debris, Animal Burrows None evident

(3) Sloughing, Subsidence or Depressions None observed

(4) Surface Cracks or Movement at Toe Concrete spillway apron is cracked,
broken and deteriorated

(5) Seepage None apparent

(6) External Drainage System (Ditches, Trenches, Blanket) None observed

(7) Condition Around Outlet Structure See d.(4) above

(8) Seepage Beyond Toe None evident

e. Abutments - Embankment Contact

Right: good condition

Left: good condition

(1) Erosion at Contact None apparent

(2) Seepage Along Contact None observed

3) Drainage System

a. Description of System Broad-crested concrete weir and discharge conveyance channel excavated into earth

b. Condition of System Good; except for the deteriorated concrete apron

c. Discharge from Drainage System Approximately 14 foot drop from weir to discharge channel (See sketch in Appendix G)

4) Instrumentation (Monumentation/Surveys, Observation Wells, Weirs, Piezometers, Etc.)
None observed

5) Reservoir

- a. Slopes Moderate valley slopes with Chenango County Road 35
following the south edge of the impoundment
- b. Sedimentation Possible accumulation of sediment behind the dam
- c. Unusual Conditions Which Affect Dam None noted

6) Area Downstream of Dam

- a. Downstream Hazard (No. of Homes, Highways, etc.) Approximately 10 buildings
and two roads are within the dam failure flood hazard area
- b. Seepage, Unusual Growth None observed
- c. Evidence of Movement Beyond Toe of Dam None evident
- d. Condition of Downstream Channel Good; presently stable, no aggradation
or degradation

7) Spillway(s) (Including Discharge Conveyance Channel)

Principal spillway and discharge conveyance channel

- a. General Principal spillway and discharge conveyance channel handle
all flows
- b. Condition of Principal Spillway Good; no signs of deterioration except
for the concrete apron which is cracked and broken

c. Condition of Emergency Spillway Not applicable

d. Condition of Discharge Conveyance Channel Good condition, presently stable

8) Reservoir Drain/Outlet

Type: Pipe X Conduit _____ Other _____

Material: Concrete _____ Metal Cast iron Other _____

Size: 6 inch Length Unknown

Invert Elevations: Entrance Unknown Exit Unknown

Physical Condition (Describe): Unobservable

Material: Cast iron

Joints: Mechanical and push-on Alignment _____

Structural Integrity: Good; except there was a crack in the casing of one of the 6 inch gate valves

Hydraulic Capability: Good; the primary purpose of the pipe is for water supply and distribution for the Town of Guilford

Means of Control: Gate _____ Valve 6 inch gate valve Uncontrolled

Operation: Operable X Inoperable _____ Uncontrolled _____

Present Condition (Describe): Good; except for the crack noted above

9) Structural

- a. Concrete Surfaces Concrete of the spillway is generally in good condition;
however, the concrete apron is cracked, broken and deteriorated
- b. Structural Cracking No evidence of any structural cracks
- c. Movement - Horizontal & Vertical Alignment (Settlement) None observed
- d. Junctions with Abutments or Embankments Concrete abutments at both ends of the
spillway are in good condition.
- e. Drains - Foundation, Joint, Face None evident
- f. Water Passages, Conduits, Sluices None observed
- g. Seepage or Leakage No signs of seepage or leakage

h. Joints - Construction, etc. Good condition

i. Foundation Inaccessible

j. Abutments See 9) d. above

k. Control Gates None observed

l. Approach & Outlet Channels Not applicable

m. Energy Dissipators (Plunge Pool, etc.) None observed

n. Intake Structures Not applicable

o. Stability Appears to be stable

p. Miscellaneous No comments

10) Appurtenant Structures (Power House, Lock, Gatehouse, Other)

a. Description and Condition None observed

[illegible]

APPENDIX C

HYDROLOGIC/HYDRAULIC ENGINEERING DATA AND COMPUTATIONS

CHECK LIST FOR DAMS
HYDROLOGIC AND HYDRAULIC
ENGINEERING DATA

AREA-CAPACITY DATA:

	<u>Elevation</u> (ft.)	<u>Surface Area</u> (acres)	<u>Storage Capacity</u> (acre-ft.)
1) Top of Dam	1560.2	84	560
2) Design High Water (Max. Design Pool)	--	--	--
3) Emergency Spillway Crest	--	--	--
4) Pool Level with Flashboards	--	--	--
5) Principal Spillway Crest	1558.0	74	390

DISCHARGES:

	<u>Volume</u> (cfs)
1) Average Daily	Unknown
2) Emergency Spillway @ Maximum High Water (Top of Dam)	451
3) Emergency Spillway @ Design High Water	--
4) Principal Spillway @ Emergency Spillway Crest	--
5) Low Level Outlet @ Principal Spillway Crest	--
6) Total (of all facilities) @ Maximum High Water	451
7) Maximum Known Flood	Unknown
8) At Time of Inspection	2+

CREST:

ELEVATION: 1560.2 (NGVD)

Type Concrete

Width 8.3 feet

Length 62 feet

Spillover Concrete spillway weir

Location Right abutment

SPILLWAY:

PRINCIPAL

EMERGENCY

1558.0 (NGVD)

Elevation

Broad-crested weir

Type

8.3 feet

Width

Type of Control

Weir

Uncontrolled

--

Controlled

None

Type:

(Flashboards; gate)

One

Number

43.5 foot long weir

Size/Length

Concrete

Invert Material

Continuously

Anticipated Length
of Operating Service

Unknown

Chute Length

Unknown

Height Between
Spillway Crest
& Approach Channel
Invert (Weir Flow)

Type: _____

Location: _____

Records:

Date Unknown _____

Max. Reading Unknown _____

FLOOD WATER CONTROL SYSTEM:

Warning System None in effect _____

Method of Controlled Releases (mechanisms) One 6 inch gate valve is used to
control the flow of water to the distribution system; the other may be used
as a reservoir drain.

DRAINAGE AREA: 1430 acres = 2.23 square miles

DRAINAGE BASIN RUNOFF CHARACTERISTICS:

Land Use - Type Rural, agriculture

Terrain - Relief Rolling uplands

Surface - Soil Glacial till

Runoff Potential (existing or planned extensive alterations to existing surface or subsurface conditions)

Primarily open fields with scattered woodlands; glacial till soils;

average watershed slope is 5 percent; a number of residential homes

(Guilford) and roadways.

Potential Sedimentation problem areas (natural or man-made; present or future)

Possible surface erosion from agricultural fields during fallow periods

Potential Backwater problem areas for levels at maximum storage capacity including surcharge storage:

None

Dikes - Floodwalls (overflow & non-overflow) - Low reaches along the reservoir perimeter:


Location: None

Elevation:

Reservoir:

Length @ Maximum Pool 2700+ feet = 0.5 miles (Miles)


Length of Shoreline (@ Spillway Crest) 7800+ feet = 1.5 miles (Miles)



WATERSHED MAP

**GUILFORD LAKE DAM
INVENTORY No. NY 1483**

**SUSQUEHANNA RIVER BASIN
CHENANGO COUNTY
GUILFORD, NEW YORK**



FLAHERTY • GIAVARA ASSOCIATES, P.C.

CALCULATIONS



WATERSHED DATA FOR HEC-1 SNYDER HYDROGRAPH

1) Time To Peak (T_p)

$$L = 10,000 \text{ ft} = 1.89 \text{ miles}$$

$$L_c = 3,500 \text{ ft} = 0.66 \text{ miles}$$

$$C_T = 2.0 \text{ for average slopes}$$

$$T_p = C_T (L L_c)^{0.3}$$

$$= 2.0 (1.89 \times 0.66)^{0.3} = 2.14 \text{ Hours}$$

$$L_r = \frac{T_p}{5.5} = \frac{2.14}{5.5} = 0.39 \quad \text{USE } T_R = 0.5$$

$$T_{pR} = T_p + 0.25 (T_R - L_r)$$

$$= 2.14 + 0.25 (0.5 - 0.39) = 2.17 \text{ Hours}$$

2) $C_p = 0.63$ for Highland Area

3) % Impervious

$$\text{Roads} - 23,000 \text{ LF} \times 25' = 575,000 \text{ ft}^2$$

$$\text{Houses} - \pm 70 @ 1000 \text{ ft}^2 = \underline{70,000 \text{ ft}^2}$$

$$645,000 \text{ ft}^2$$

$$645,000 \text{ ft}^2 = 14.8 \text{ ACRES}$$

$$\frac{14.8 \text{ ACRES}}{1429.8 \text{ ACRES}} = 1.0\%$$

4) WATERSHED AREA

$$1429.8 \text{ ACRES} / 640 = 2.23 \text{ Square Miles}$$

BASED ON 1" = 2000' USGS map

PROJECT CORPS DAMS
NY 1483



FLAHERTY-GIAVARA ASSOCIATES
ENVIRONMENTAL DESIGN CONSULTANTS
ONE COLUMBUS PLAZA, NEW HAVEN, CONN. 06510/203/789-1200

SHEET NO. 2 OF 5
BY RAC DATE 4-7-81
CHK'D. BY TLW DATE 6-23-81

5) RAINFALL DATA - (FROM HYDROMETEOROLOGICAL
REPORT NO. 33)

24 Hr PMP = 20.3 inches for 200 square miles

DURATION (HRS)

ADJ FACTOR %

6

111

12

122

24

133

48

143


PROJECT CORPS Dam
NY 1483



FLAHERTY-GIAVARA ASSOCIATES
 ENVIRONMENTAL DESIGN CONSULTANTS
 ONE COLUMBUS PLAZA, NEW HAVEN, CONN. 06510/203/789-1280

SHEET NO. 3 OF 5
 BY RAC DATE 4-7-81
 CHK'D. BY TLW DATE 6-23-81

STAGE DISCHARGE DATA



<u>STAGE</u>	<u>$Q = 3 L H^{1.5}$</u>	<u>$Q = 2.5 L H^{1.5}$</u>	<u>DISCHARGE</u>
1558.0	0	-	0
1558.5	$3(45)(.5)^{1.5}$	-	47.7
1559.0	$3(45)(1)^{1.5}$	-	135.0
1559.5	$3(45)(1.5)^{1.5}$	-	248.0
1559.8	$3(45)(1.8)^{1.5}$	-	326.0
1560.0	$3(45)(2)^{1.5} + 3(1.5)(.2)^{1.5}$	$2.5(14)(.2)^{1.5}$	385.4
1560.2	$3(45)(2.2)^{1.5} + 3(1.5)(.4)^{1.5}$	$2.5(14)(.4)^{1.5}$	450.5
1560.5	$3(45)(2.5)^{1.5} + 3(1.5)(.7)^{1.5} + 3(1.5)(.3)^{1.5}$	$2.5(14)(.7)^{1.5}$	557.5
1561.0	$3(45)(3)^{1.5} + 3(1.5)(1.2)^{1.5} + 3(1.5)(.8)^{1.5}$	$2.5(14)(1.2)^{1.5}$	756.6
1570.0	$3(45)(2)^{1.5} + 3(1.5)(10.2)^{1.5} + 3(1.5)(.8)^{1.5}$	$2.5(14)(10.2)^{1.5}$	7036.7 5896.5

PROJECT CORPS DAMS
44 1483




FLAHERTY-GIAVARA ASSOCIATES
ENVIRONMENTAL DESIGN CONSULTANTS
ONE COLUMBUS PLAZA, NEW HAVEN, CONN. 06510/203/788-1280

SHEET NO. 4 OF 5
BY RAC DATE 4-7-81
CHK'D. BY TLW DATE 6-23-81

STAGE DISCHARGE CURVE

SPILLWAY SECTION



PROJECT CORPS DAM
SULFORD LAKE DAM
NY 1483




FLAHERTY-GIAVARA ASSOCIATES
ENVIRONMENTAL DESIGN CONSULTANTS
ONE COLUMBUS PLAZA, NEW HAVEN, CONN. 06510/203/789-1280

SHEET NO. 5 OF 5
BY RAC DATE 5-8-81
CHK'D. BY TLW DATE 6-23-81

STAGE DISCHARGE CURVE

SPILLWAY & DAM OVERTOPPING



HEC-1 FLOOD HYDROGRAPH COMPUTATIONS

FLAHERTY GIAVARA ASSOCIATES, P. C.
FLOOD HYDROGRAPH PACKAGE (HEC-1)
DAM SAFETY VERSION JULY 1978
LAST MODIFICATION 26 FEB 79

A1 NATIONAL DAM INSPECTION PROGRAM, PHASE I REPORT, CORPS OF ENGINEERS - NEW YORK DISTRICT
A2 DAM INVENTORY NO. NY 1483, GUILFORD LAKE DAM, CHENANGO COUNTY, NEW YORK, APRIL 7, 1981
A3 PREPARED BY FLAHERTY GIAVARA ASSOCIATES, P. C.; ONE COLUMBUS PLAZA, NEW HAVEN, CONNECTICUT 06510

1 1 0.10 0.17 0.18 0.17 0.20 0.30 1.00
2 2 0.10 0.17 0.18 0.17 0.20 0.30 1.00
3 3 0.10 0.17 0.18 0.17 0.20 0.30 1.00
4 4 0.10 0.17 0.18 0.17 0.20 0.30 1.00
5 5 0.10 0.17 0.18 0.17 0.20 0.30 1.00
6 6 0.10 0.17 0.18 0.17 0.20 0.30 1.00
7 7 0.10 0.17 0.18 0.17 0.20 0.30 1.00
8 8 0.10 0.17 0.18 0.17 0.20 0.30 1.00
9 9 0.10 0.17 0.18 0.17 0.20 0.30 1.00
10 10 0.10 0.17 0.18 0.17 0.20 0.30 1.00
11 11 0.10 0.17 0.18 0.17 0.20 0.30 1.00
12 12 0.10 0.17 0.18 0.17 0.20 0.30 1.00
13 13 0.10 0.17 0.18 0.17 0.20 0.30 1.00
14 14 0.10 0.17 0.18 0.17 0.20 0.30 1.00
15 15 0.10 0.17 0.18 0.17 0.20 0.30 1.00
16 16 0.10 0.17 0.18 0.17 0.20 0.30 1.00
17 17 0.10 0.17 0.18 0.17 0.20 0.30 1.00
18 18 0.10 0.17 0.18 0.17 0.20 0.30 1.00
19 19 0.10 0.17 0.18 0.17 0.20 0.30 1.00
20 20 0.10 0.17 0.18 0.17 0.20 0.30 1.00
21 21 0.10 0.17 0.18 0.17 0.20 0.30 1.00
22 22 0.10 0.17 0.18 0.17 0.20 0.30 1.00
23 23 0.10 0.17 0.18 0.17 0.20 0.30 1.00
24 24 0.10 0.17 0.18 0.17 0.20 0.30 1.00
25 25 0.10 0.17 0.18 0.17 0.20 0.30 1.00

PREVIEW OF SEQUENCE OF STREAM NETWORK CALCULATIONS
RUNOFF HYDROGRAPH AT
ROUTE HYDROGRAPH TO
END OF NETWORK

FLOOD HYDROGRAPH PACKAGE (HEC-1)
DAM SAFETY VERSION JULY 1978
LAST MODIFICATION 26 FEB 79

RUN DATE: 8/21/
TIME: 6:39 AM

NATIONAL DAM INSPECTION PROGRAM, PHASE I REPORT, CORPS OF ENGINEERS - NEW YORK DISTRICT
DAM INVENTORY NO. NY 1483, GUILFORD LAKE DAM, CHENANGO COUNTY, NEW YORK, APRIL 7, 1981
PREPARED BY FLAHERTY GIAVARA ASSOCIATES, P. C.; ONE COLUMBUS PLAZA, NEW HAVEN, CONNECTICUT 06510

NO 120 NWS 0 MIN 30 IDAY 0 JOPER 5 JOB SPECIFICATION IHR 0 NWT 0 IMIN 0 LROPT 0 METRC 0 TRACE 0 IPLI 2 IPRI 0 NSTAN 0

MULTI-PLAN ANALYSES TO BE PERFORMED

RTIDS=	0.10	0.15	0.16	0.17	0.18	0.19	0.20	0.50	1.00
NPLAN= 1 NRTIO= 9 LRTIO= 1									

德意志銀行

新新新新新新新新新新

市市市市市市市市市

新行方廣步新行新行

“...the fact that the defendant was not present at the time of the shooting...”

SUB-AREA RUNOFF COMPUTATION

INFLW	HYDROGRAPH	SNYDER	METHOD	ITYPE	JPLT	JPRF	INAME	ISTAGE	IAUTO
	18TAQ	ICOMP	IECON	0	0	0	1	0	0

HYDRO	IUNG	TAREA	SNAP	TRSDA	TRSPC	RATIO	IBNOH	ISANE	LOCAL
-------	------	-------	------	-------	-------	-------	-------	-------	-------

PRECIP DATA

TRSPC COMPUTED BY THE PROGRAM IS 0.800

[illegible]

UNIT HYDROGRAPH DATA NTA= 0
2 17 CP=0.63

RECESSION DATA		NOTES
STRIP#	-2.00	1. 50
GRCSN#	-0.10	2. 10
AND TO BE	TCN	3. 17
AND TO BE	TCN	4. 17
AND TO BE	TCN	5. 17
AND TO BE	TCN	6. 17
AND TO BE	TCN	7. 17
AND TO BE	TCN	8. 17
AND TO BE	TCN	9. 17
AND TO BE	TCN	10. 17
AND TO BE	TCN	11. 17
AND TO BE	TCN	12. 17
AND TO BE	TCN	13. 17
AND TO BE	TCN	14. 17
AND TO BE	TCN	15. 17
AND TO BE	TCN	16. 17
AND TO BE	TCN	17. 17
AND TO BE	TCN	18. 17
AND TO BE	TCN	19. 17
AND TO BE	TCN	20. 17
AND TO BE	TCN	21. 17
AND TO BE	TCN	22. 17
AND TO BE	TCN	23. 17
AND TO BE	TCN	24. 17
AND TO BE	TCN	25. 17
AND TO BE	TCN	26. 17
AND TO BE	TCN	27. 17
AND TO BE	TCN	28. 17
AND TO BE	TCN	29. 17
AND TO BE	TCN	30. 17
AND TO BE	TCN	31. 17
AND TO BE	TCN	32. 17
AND TO BE	TCN	33. 17
AND TO BE	TCN	34. 17
AND TO BE	TCN	35. 17
AND TO BE	TCN	36. 17
AND TO BE	TCN	37. 17
AND TO BE	TCN	38. 17
AND TO BE	TCN	39. 17
AND TO BE	TCN	40. 17
AND TO BE	TCN	41. 17
AND TO BE	TCN	42. 17
AND TO BE	TCN	43. 17
AND TO BE	TCN	44. 17
AND TO BE	TCN	45. 17
AND TO BE	TCN	46. 17
AND TO BE	TCN	47. 17
AND TO BE	TCN	48. 17
AND TO BE	TCN	49. 17
AND TO BE	TCN	50. 17
AND TO BE	TCN	51. 17
AND TO BE	TCN	52. 17
AND TO BE	TCN	53. 17
AND TO BE	TCN	54. 17
AND TO BE	TCN	55. 17
AND TO BE	TCN	56. 17
AND TO BE	TCN	57. 17
AND TO BE	TCN	58. 17
AND TO BE	TCN	59. 17
AND TO BE	TCN	60. 17
AND TO BE	TCN	61. 17
AND TO BE	TCN	62. 17
AND TO BE	TCN	63. 17
AND TO BE	TCN	64. 17
AND TO BE	TCN	65. 17
AND TO BE	TCN	66. 17
AND TO BE	TCN	67. 17
AND TO BE	TCN	68. 17
AND TO BE	TCN	69. 17
AND TO BE	TCN	70. 17
AND TO BE	TCN	71. 17
AND TO BE	TCN	72. 17
AND TO BE	TCN	73. 17
AND TO BE	TCN	74. 17
AND TO BE	TCN	75. 17
AND TO BE	TCN	76. 17
AND TO BE	TCN	77. 17
AND TO BE	TCN	78. 17
AND TO BE	TCN	79. 17
AND TO BE	TCN	80. 17
AND TO BE	TCN	81. 17
AND TO BE	TCN	82. 17
AND TO BE	TCN	83. 17
AND TO BE	TCN	84. 17
AND TO BE	TCN	85. 17
AND TO BE	TCN	86. 17
AND TO BE	TCN	87. 17
AND TO BE	TCN	88. 17
AND TO BE	TCN	89. 17
AND TO BE	TCN	90. 17
AND TO BE	TCN	91. 17
AND TO BE	TCN	92. 17
AND TO BE	TCN	93. 17
AND TO BE	TCN	94. 17
AND TO BE	TCN	95. 17
AND TO BE	TCN	96. 17
AND TO BE	TCN	97. 17
AND TO BE	TCN	98. 17
AND TO BE	TCN	99. 17
AND TO BE	TCN	100. 17

UNIT HYDROGRAPH 24 END-OF-PERIOD ORDINATES: LAG= 2.19 HOURS: CPM D.64 VOL= 1.00
142. 271. 375. 413. 367. 288. 223. 172. 133.
10.

[illegible]

[illegible]

SUM	23.22	19.95	3.67	61679.
	590.77	497.11	93.11	1746.53

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL	VOLUME
CFB	4839	3389	1223	513		61584
CMB	137	96	33	17		1744
INCHES		14.14	20.40	21.41		21.41
MM		359.07	518.28	543.76		543.76
CU-FT		1680	2442	2543		2543
AC-H		2073	2772	3137		3137

◆ ◆ ◆

STATION 11

INFLOW(I), OUTFLOW(O) AND OBSERVED FLOW(##)

[illegible]

[illegible]

- 15

HYDROGRAPH AT STA 1 FOR PLAN 1, RTIO 3

HYDROGRAPH AT STA 1 FOR PLAN 1, RTIO 8

CFB	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL	VOLUME
CBS	2416.	1694.	411.	257.	30792.	872.
INCHES	68.	48.	17.	7.		
MM		179.53	10.20	10.70		271.88
CU-FT		77.07	256.14	271.88		1272.
AC-F		840.	1213.	1272.		1569.
THOUS CU YD		1036.	1496.	1569.		

HYDROGRAPH AT STA 1 FOR PLAN 1, RTIO 9

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL	PER ONE
CFB	4832	3389	1223	513	81584	
CFB	137	96	35	13	1744	
INCHES		20.40			21.41	
MM		397.07	518.28	543.76	543.76	
CU-FT		1680	2426	3139	3139	
AC-M		2073	2972			
THOUS						

HYDROGRAPH ROUTING

RESERVOIR ROUTING - MODIFIED PLUS METHOD

UPRT INAME I STAGE I AUTO

QLOSS	CLOSS	AVG
0.0	0.000	0.00

IPMP^D

LSTR 0

;

END-OF-PERIOD HYDROGRAPH ORDINATES


C-20

[illegible]

QVF

[illegible]

18 00 3601
18 30 3701
19 30 3801
20 30 3901
21 30 4001
22 30 4101
23 30 4201
24 30 4301
25 30 4401
26 30 4501
27 30 4601
28 30 4701
29 30 4801
30 30 4901
31 30 5001
32 30 5101
33 30 5201
34 30 5301
35 30 5401
36 30 5501
37 30 5601
38 30 5701
39 30 5801
40 30 5901
41 30 6001
42 30 6101
43 30 6201
44 30 6301
45 30 6401
46 30 6501
47 30 6601
48 30 6701
49 30 6801
50 30 6901
51 30 7001
52 30 7101
53 30 7201
54 30 7301
55 30 7401
56 30 7501
57 30 7601
58 30 7701
59 30 7801
60 30 7901
61 30 8001
62 30 8101
63 30 8201
64 30 8301
65 30 8401
66 30 8501
67 30 8601
68 30 8701
69 30 8801
70 30 8901
71 30 9001
72 30 9101
73 30 9201
74 30 9301



OVN

STATION 1, PLAN 1, RATIO 2
END-OF-PERIOD HYDROGRAPH ORDINATES

STATION	1	2	3	4	5	6	7	8	9	10	11	12
OUTFLOW	0000	0000	0000	0000	0000	0000	0000	0000	0000	0000	0000	0000
STORAGE	0000	0000	0000	0000	0000	0000	0000	0000	0000	0000	0000	0000
1	117	148	191	117	148	191	117	148	191	117	148	191
2	117	148	191	117	148	191	117	148	191	117	148	191
3	117	148	191	117	148	191	117	148	191	117	148	191
4	117	148	191	117	148	191	117	148	191	117	148	191
5	117	148	191	117	148	191	117	148	191	117	148	191
6	117	148	191	117	148	191	117	148	191	117	148	191
7	117	148	191	117	148	191	117	148	191	117	148	191
8	117	148	191	117	148	191	117	148	191	117	148	191
9	117	148	191	117	148	191	117	148	191	117	148	191
10	117	148	191	117	148	191	117	148	191	117	148	191
11	117	148	191	117	148	191	117	148	191	117	148	191
12	117	148	191	117	148	191	117	148	191	117	148	191

10.	11.	12.	13.	14.	15.	16.	17.	18.	19.	20.	21.	22.	23.	24.	25.	26.	27.	28.	29.	30.	31.	32.	33.	34.	35.	36.	37.	38.	39.	40.	41.	42.	43.	44.	45.	46.	47.	48.	49.	50.	51.	52.	53.	54.	55.	56.	57.	58.	59.	60.	61.	62.	63.	64.	65.	66.	67.	68.	69.	70.	71.	72.	73.	74.	75.	76.	77.	78.	79.	80.	81.	82.	83.	84.	85.	86.	87.	88.	89.	90.	91.	92.	93.	94.	95.	96.	97.	98.	99.	100.
10.	11.	12.	13.	14.	15.	16.	17.	18.	19.	20.	21.	22.	23.	24.	25.	26.	27.	28.	29.	30.	31.	32.	33.	34.	35.	36.	37.	38.	39.	40.	41.	42.	43.	44.	45.	46.	47.	48.	49.	50.	51.	52.	53.	54.	55.	56.	57.	58.	59.	60.	61.	62.	63.	64.	65.	66.	67.	68.	69.	70.	71.	72.	73.	74.	75.	76.	77.	78.	79.	80.	81.	82.	83.	84.	85.	86.	87.	88.	89.	90.	91.	92.	93.	94.	95.	96.	97.	98.	99.	100.
10.	11.	12.	13.	14.	15.	16.	17.	18.	19.	20.	21.	22.	23.	24.	25.	26.	27.	28.	29.	30.	31.	32.	33.	34.	35.	36.	37.	38.	39.	40.	41.	42.	43.	44.	45.	46.	47.	48.	49.	50.	51.	52.	53.	54.	55.	56.	57.	58.	59.	60.	61.	62.	63.	64.	65.	66.	67.	68.	69.	70.	71.	72.	73.	74.	75.	76.	77.	78.	79.	80.	81.	82.	83.	84.	85.	86.	87.	88.	89.	90.	91.	92.	93.	94.	95.	96.	97.	98.	99.	100.

PEAK OUTFLOW IS 407. AT TIME 44.00 HOURS

CFR	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
407.	407.	347.	167.	68.	8202.
CMR	12.	10.	5.	2.	238.
INCHES	1.45	1.45	2.79	2.85	2.85
MM	36.81	36.81	70.78	72.42	72.42
AC-FT	172.	172.	331.	339.	339.
THOUS CU M	213.	213.	409.	418.	418.


DVF

STATION 1
INFLW(1), OUTFLOW(1) AND OBSERVED FLOW(1)

	100.	200.	300.	400.	500.	600.	700.	800.	900.	0.
0.1										
1.1										
2.1										
3.1										
4.1										
5.1										
6.1										
7.1										
8.1										
9.1										
10.1										
11.1										
12.1										
13.1										
14.1										
15.1										
16.1										
17.1										
18.1										
19.1										
20.1										
21.1										
22.1										
23.1										
24.1										
25.1										
26.1										
27.1										
28.1										
29.1										
30.1										
31.1										
32.1										
33.1										
34.1										
35.1										
36.1										
37.1										
38.1										
39.1										
40.1										
41.1										
42.1										
43.1										
44.1										
45.1										
46.1										
47.1										
48.1										
49.1										
50.1										
51.1										
52.1										
53.1										
54.1										
55.1										
56.1										
57.1										
58.1										
59.1										
60.1										
61.1										
62.1										
63.1										
64.1										
65.1										
66.1										
67.1										
68.1										
69.1										
70.1										
71.1										
72.1										
73.1										
74.1										
75.1										
76.1										
77.1										
78.1										
79.1										
80.1										
81.1										
82.1										
83.1										
84.1										
85.1										
86.1										
87.1										
88.1										
89.1										
90.1										
91.1										
92.1										
93.1										
94.1										
95.1										
96.1										
97.1										
98.1										
99.1										
100.1										

FLAHERTY GIAVARA ASSOCIATES, P. C.

[illegible]



ENDS

STATION 11 PLAN 17 RATIO 3
END-OF-PERIOD HYDROGRAPH ORDINATES

000000000000
000000000000
000000000000
000000000000
OUTFLOW
000000000000
000000000000
000000000000
000000000000

[illegible]

PEAK OUTFLOW IS 440. AT TIME 44.00 HOURS

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL	VOLUME
CBS	440	374	179	73	784	249
CBS	12	11	58	3	85	3
INCHES		1.56	2.58	3.05		
MM		39.65	75.80	77.56		
CU-FT		186	355	363		
THOUS CU FT		229	438	448		

QVE

STATION 1


INFLOW(I), OUTFLOW(O) AND OBSERVED FLOW(O*)

[illegible]

FLAHERTY O'AVARA ASSOCIATES, P. C.

6.6	7.7	8.8	9.9	10.0	11.1	12.2	13.3	14.4	15.5	16.6	17.7	18.8	19.9	20.0	21.1	22.2	23.3	24.4	25.5	26.6	27.7	28.8	29.9	30.0	31.1	32.2	33.3	34.4	35.5	36.6	37.7	38.8	39.9	40.0	41.1	42.2	43.3	44.4	45.5	46.6	47.7	48.8	49.9	50.0	51.1	52.2	53.3	54.4	55.5	56.6	57.7	58.8	59.9	60.0	61.1	62.2	63.3	64.4	65.5	66.6	67.7	68.8	69.9	70.0	71.1	72.2	73.3	74.4	75.5	76.6	77.7	78.8	79.9	80.0	81.1	82.2	83.3	84.4	85.5	86.6	87.7	88.8	89.9	90.0	91.1	92.2	93.3	94.4	95.5	96.6	97.7	98.8	99.9	100.0
-----	-----	-----	-----	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	-------

11 00 70
12 00 71
13 00 72
14 00 73
15 00 74
16 00 75
17 00 76
18 00 77
19 00 78
20 00 79
21 00 80
22 00 81
23 00 82
24 00 83
25 00 84
26 00 85
27 00 86
28 00 87
29 00 88
30 00 89
31 00 90
32 00 91
33 00 92
34 00 93
35 00 94
36 00 95
37 00 96
38 00 97
39 00 98
40 00 99
41 00 100
42 00 101
43 00 102
44 00 103
45 00 104
46 00 105
47 00 106
48 00 107
49 00 108
50 00 109
51 00 110
52 00 111
53 00 112
54 00 113
55 00 114
56 00 115
57 00 116
58 00 117
59 00 118
60 00 119
61 00 120



STATION 1: PLAN 1: RATIO 4

OVN

END-OF-PERIOD HYDROGRAPH ORDINATES

• END •

STATION

```

INFLOW(I), BUTFLOW(I) AND OBSERVED FLOW(I)

```

PAGE 0021

[illegible]

FLAHERTY GIAVARA ASSOCIATES, P. C.

PAGE 0022

[illegible]

7-37

#QW#

STATION 1, PLAN 1, RATIO 5
END-OF-PERIOD HYDROGRAPH ORDINATES

[illegible]

PEAK OUTFLOW IS 510. AT TIME 14.00 HOURS.

#JAD#

STATION

INFLOW(I), OUTFLOW(O) AND OBSERVED FLOW(*)

0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50
0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50
0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50
0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50
0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50
0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50
0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50
0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50
0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50
0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50
0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50
0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	2																							

23 00 4610
23 30 4710
00 30 4810
01 30 501
1 30 511
1 30 521
1 30 531
1 30 541
1 30 551
1 30 561
1 30 571
1 30 581
1 30 591
1 30 601
1 30 6101
1 30 6201
1 30 6301
1 30 64 01
1 30 65 00 00 00 00
1 30 66 00 00 00 00
1 30 67 00 00 00
1 30 68 00 00 00
1 30 69 00 00 00
1 30 70 00 00 00
1 30 71 00 00 00
1 30 72 00 00 00
1 30 73 00 00 00
1 30 74 00 00 00
1 30 75 00 00 00
1 30 76 00 00 00
1 30 77 00 00 00
1 30 78 00 00 00
1 30 79 00 00 00
1 30 80 00 00 00
1 30 81 00 00 00
1 30 82 00 00 00
1 30 83 00 00 00
1 30 84 00 00 00
1 30 85 00 00 00
1 30 86 00 00 00
1 30 87 00 00 00
1 30 88 00 00 00
1 30 89 00 00 00
1 30 90 00 00 00
1 30 91 00 00 00
1 30 92 00 00 00
1 30 93 00 00 00
1 30 94 00 00 00
1 30 95 00 00 00
1 30 96 00 00 00
1 30 97 00 00 00
1 30 98 00 00 00
1 30 99 00 00 00
1 30 100 00 00 00
1 30 101 00 00 00
1 30 102 00 00 00
1 30 103 00 00 00

STATION 1, PLAN 1, RATIO 6
END-OF-PERIOD-HYDROGRAPH-ORDINATE

OUTFLOW	STORAGE	STAGE
00000455	00000544	00000544
14	12	12
141	106	106
282	172	172
206	101	101
110	186	186
00000455	00000544	00000544
16	12	12
141	106	106
282	172	172
206	101	101
110	186	186
00000455	00000544	00000544
17	13	13
221	106	106
447	172	172
191	101	101
104	186	186
00000455	00000544	00000544
19	13	13
242	106	106
418	172	172
177	101	101
00000455	00000544	00000544
26	13	13
440	106	106
344	172	172
154	101	101
190	186	186
00000455	00000544	00000544
41	14	14
534	106	106
282	172	172
132	101	101
181	186	186
00000455	00000544	00000544
58	14	14
545	106	106
298	172	172
128	101	101
177	186	186
00000455	00000544	00000544
82	14	14
537	106	106
240	172	172
121	101	101
174	186	186
00000455	00000544	00000544
116	14	14
515	106	106
222	172	172
115	101	101
170	186	186
00000455	00000544	00000544
116	14	14
515	106	106
222	172	172
115	101	101
170	186	186
00000455	00000544	00000544
116	14	14
515	106	106
222	172	172
115	101	101
170	186	186
00000455	00000544	00000544
116	14	14
515	106	106
222	172	172
115	101	101
170	186	186
00000455	00000544	00000544
116	14	14
515	106	106
222	172	172
115	101	101
170	186	186
00000455	00000544	00000544
116	14	14
515	106	106
222	172	172
115	101	101
170	186	186
00000455	00000544	00000544
116	14	14
515	106	106
222	172	172
115	101	101
170	186	186
00000455	00000544	00000544
116	14	14
515	106	106
222	172	172
115	101	101
170	186	186
00000455	00000544	00000544
116	14	14
515	106	106
222	172	172
115	101	101
170	186	186
00000455	00000544	00000544
116	14	14
515	106	106
222	172	172
115	101	101
170	186	186
00000455	00000544	00000544
116	14	14
515	106	106
222	172	172
115	101	101
170	186	186
00000455	00000544	00000544
116	14	14
515	106	106
222	172	172
115	101	101
170	186	186
00000455	00000544	00000544
116	14	14
515	106	106
222	172	172
115	101	101
170	186	186
00000455	00000544	00000544
116	14	14
515	106	106
222	172	172
115	101	101
170	186	186
00000455	00000544	00000544
116	14	14
515	106	106
222	172	172
115	101	101
170	186	186
00000455	00000544	00000544
116	14	14
515	106	106
222	172	172
115	101	101
170	186	186
00000455	00000544	00000544
116	14	14
515	106	106
222	172	172
115	101	101
170	186	186
00000455	00000544	00000544
116	14	14
515	106	106
222	172	172
115	101	101
170	186	186
00000455	00000544	00000544
116	14	14
515	106	106
222	172	172
115	101	101
170	186	186
00000455	00000544	00000544
116	14	14
515	106	106
222	172	172
115	101	101
170	186	186
00000455	00000544	00000544
116	14	14
515	106	106
222	172	172
115	101	101
170	186	186
00000455	00000544	00000544
116	14	14
515	106	106
222	172	172
115	101	101
170	186	186
00000455	00000544	00000544
116	14	14
515	106	106
222	172	172
115	101	101
170	186	186
00000455	00000544	00000544
116	14	14
515	106	106
222	172	172
115	101	101
170	186	186
00000455	00000544	00000544
116	14	14
515	106	106
222	172	172
115	101	101
170	186	186
00000455	00000544	00000544
116	14	14
515	106	106
222	172	172
115	101	101
170	186	186
00000455	00000544	00000544
116	14	14
515	106	106
222	172	172
115	101	101
170	186	186
00000455	00000544	00000544
116	14	14
515	106	106
222	172	172
115	101	101
170	186	186
00000455	00000544	00000544
116	14	14
515	106	106
222	172	172
115	101	101
170	186	186
00000455	00000544	00000544
116	14	14
515	106	106
222	172	172
115	101	101
170	186	186
00000455	00000544	00000544
116	14	14
515	106	106
222	172	172
115	101	101
170	186	186
00000455	00000544	00000544
116	14	14
515	106	106
222	172	172
115	101	101
170	186	186
00000455	00000544	00000544
116	14	14
515	106	106
222	172	172
115	101	101
170	186	186
00000455	00000544	00000544
116	14	14
515	106	106
222	172	172
115	101	101
170	186	186
00000455	00000544	00000544
116	14	14
515	106	106
222	172	172
115	101	101
170	186	186
00000455	00000544	00000544
116	14	14
515	106	106
222	172	172
115	101	101
170	186	186
00000455	00000544	00000544
116	14	14
515	106	106
222	172	172
115	101	101
170	186	186
00000455	00000544	00000544
116	14	14
515	106	106
222	172	172
115	101	101
170	186	186
00000455	00000544	00000544
116	14	14
515	106	106
222	172	172
115	101	101
170	186	186
00000455	00000544	00000544
116	14	14
515	106	106
222	172	172
115	101	101
170	186	186
00000455	00000544	00000544
116	14	14
515	106	106
222	172	172
115	101	101
170	186	186
00000455	00000544	00000544
116	14	14
515	106	106
222	172	172
115	101	101
170	186	186
00000455	00000544	00000544
116	14	14
515	106	106
222	172	172
115	101	101
170	186	186
00000455	00000544	00000544
116	14	14
515	106	106
222	172	172
115	101	101
170	186	186
00000455	00000544	00000544
116	14	14
515	106	106
222	172	172
115	101	101
170	186	186
00000455	00000544	00000544
116	14	14
515	106	106
222	172	172
115	101	101
170	186	186
00000455	00000544	00000544
116	14	14
515	106	106
222	172	172
115	101	101
170	186	186
00000455	00000544	00000544
116	14	14
515	106	106
222	172	172
115	101	101
170	186	186
00000455	00000544	00000544
116	14	14
515	106	106
222	172	172
115	101	101
170	186	186
00000455	00000544	00000544
116	14	14
515	106	106
222	172	172
115	101	101
170	186	186
00000455	00000544	00000544
116	14	14
515	106	106
222	172	172
115	101	101
170	186	186
00000455	00000544	00000544
116	14	14
515	106	106
222	172	172
115	101	101
170	186	186
00000455	00000544	00000544
116	14	14
515	106	106
222	172	172
115	101	101
170	186	186
00000455	00000544	00000544
116	14	14
515	106	106
222	172	172
115	101	101
170	186	186
00000455	00000544	00000544
116	14	14
515	106	106
222	172	172
115	101	101
170	186	186
00000455	00000544	00000544
116	14	14
515	106	106
222	172	172
115	101	101
170	186	186
00000455	00000544	00000544
116	14	14
515	106	106
222	172	172
115	101	101
170	186	186
00000455	00000544	00000544
116	14	14
515	106	106
222	172	172
115	101	101
170	186	186
00000455	00000544	00000544
116	14	14
515	106	106
222	172	172
115	101	101
170	186	186
00000455	00000544	00000544
116	14	14
515	106	106
222	172	172
115	101	101
170	186	186
00000455	00000544	00000544
116	14	14
515	106</	

[illegible]

1. *Chlorophyll a* (Chl *a*)

2. *Chlorophyll b* (Chl *b*)

3. *Carotenoids* (Chl *c*)

4. *Phycocyanin* (Chl *d*)

5. *Phaeophytin* (Chl *e*)

6. *Phaeoerythrin* (Chl *f*)

7. *Phaeopigment* (Chl *g*)

8. *Phaeo-*Chl* *a** (Chl *h*)

9. *Phaeo-*Chl* *b** (Chl *i*)

10. *Phaeo-*Chl* *c** (Chl *j*)

11. *Phaeo-*Chl* *d** (Chl *k*)

12. *Phaeo-*Chl* *e** (Chl *l*)

13. *Phaeo-*Chl* *f** (Chl *m*)

14. *Phaeo-*Chl* *g** (Chl *n*)

15. *Phaeo-*Chl* *h** (Chl *o*)

16. *Phaeo-*Chl* *i** (Chl *p*)

17. *Phaeo-*Chl* *j** (Chl *q*)

18. *Phaeo-*Chl* *k** (Chl *r*)

19. *Phaeo-*Chl* *l** (Chl *s*)

20. *Phaeo-*Chl* *m** (Chl *t*)

21. *Phaeo-*Chl* *n** (Chl *u*)

22. *Phaeo-*Chl* *o** (Chl *v*)

23. *Phaeo-*Chl* *p** (Chl *w*)

24. *Phaeo-*Chl* *q** (Chl *x*)

25. *Phaeo-*Chl* *r** (Chl *y*)

26. *Phaeo-*Chl* *s** (Chl *z*)

27. *Phaeo-*Chl* *t** (Chl *aa*)

28. *Phaeo-*Chl* *u** (Chl *ab*)

29. *Phaeo-*Chl* *v** (Chl *ac*)

30. *Phaeo-*Chl* *w** (Chl *ad*)

31. *Phaeo-*Chl* *x** (Chl *ae*)

32. *Phaeo-*Chl* *y** (Chl *af*)

33. *Phaeo-*Chl* *z** (Chl *ag*)

34. *Phaeo-*Chl* *aa** (Chl *ah*)

35. *Phaeo-*Chl* *ab** (Chl *ai*)

36. *Phaeo-*Chl* *ac** (Chl *aj*)

37. *Phaeo-*Chl* *ad** (Chl *ak*)

38. *Phaeo-*Chl* *ae** (Chl *al*)

39. *Phaeo-*Chl* *af** (Chl *am*)

40. *Phaeo-*Chl* *ag** (Chl *an*)

41. *Phaeo-*Chl* *ah** (Chl *ao*)

42. *Phaeo-*Chl* *ai** (Chl *ap*)

43. *Phaeo-*Chl* *aj** (Chl *aq*)

44. *Phaeo-*Chl* *ak** (Chl *ar*)

45. *Phaeo-*Chl* *al** (Chl *as*)

46. *Phaeo-*Chl* *am** (Chl *at*)

47. *Phaeo-*Chl* *an** (Chl *au*)

48. *Phaeo-*Chl* *ao** (Chl *av*)

49. *Phaeo-*Chl* *ap** (Chl *aw*)

50. *Phaeo-*Chl* *aq** (Chl *ax*)

51. *Phaeo-*Chl* *ar** (Chl *ay*)

52. *Phaeo-*Chl* *as** (Chl *az*)

53. *Phaeo-*Chl* *at** (Chl *ba*)

54. *Phaeo-*Chl* *au** (Chl *bb*)

55. *Phaeo-*Chl* *av** (Chl *bc*)

56. *Phaeo-*Chl* *aw** (Chl *bd*)

57. *Phaeo-*Chl* *ax** (Chl *be*)

58. *Phaeo-*Chl* *ay** (Chl *bf*)

59. *Phaeo-*Chl* *az** (Chl *bg*)

60. *Phaeo-*Chl* *ba** (Chl *bh*)

61. *Phaeo-*Chl* *bb** (Chl *bi*)

62. *Phaeo-*Chl* *bc** (Chl *bj*)

63. *Phaeo-*Chl* *bd** (Chl *bk*)

64. *Phaeo-*Chl* *be** (Chl *bl*)

65. *Phaeo-*Chl* *bf** (Chl *bm*)

66. *Phaeo-*Chl* *bg** (Chl *bn*)

67. *Phaeo-*Chl* *bh** (Chl *bo*)

68. *Phaeo-*Chl* *bi** (Chl *bp*)

69. *Phaeo-*Chl* *bj** (Chl *bq*)

70. *Phaeo-*Chl* *bk** (Chl *br*)

71. *Phaeo-*Chl* *bl** (Chl *bs*)

72. *Phaeo-*Chl* *bm** (Chl *bt*)

73. *Phaeo-*Chl* *bn** (Chl *bu*)

74. *Phaeo-*Chl* *bo** (Chl *bv*)

75. *Phaeo-*Chl* *bp** (Chl *bw*)

76. *Phaeo-*Chl* *bq** (Chl *bx*)

77. *Phaeo-*Chl* *br** (Chl *by*)

78. *Phaeo-*Chl* *bs** (Chl *bz*)

79. *Phaeo-*Chl* *bt** (Chl *ca*)

80. *Phaeo-*Chl* *bu** (Chl *cb*)

81. *Phaeo-*Chl* *bv** (Chl *cc*)

82. *Phaeo-*Chl* *bw** (Chl *cd*)

83. *Phaeo-*Chl* *bx** (Chl *ce*)

84. *Phaeo-*Chl* *by** (Chl *cf*)

85. *Phaeo-*Chl* *bz** (Chl *cg*)

86. *Phaeo-*Chl* *ca** (Chl *ch*)

87. *Phaeo-*Chl* *cb** (Chl *ci*)

88. *Phaeo-*Chl* *cc** (Chl *cj*)

89. *Phaeo-*Chl* *cd** (Chl *ck*)

90. *Phaeo-*Chl* *ce** (Chl *cl*)

91. *Phaeo-*Chl* *cf** (Chl *cm*)

92. *Phaeo-*Chl* *cg** (Chl *cn*)

93. *Phaeo-*Chl* *ch** (Chl *co*)

94. *Phaeo-*Chl* *ci** (Chl *cp*)

95. *Phaeo-*Chl* *cj** (Chl *cq*)

96. *Phaeo-*Chl* *ck** (Chl *cr*)

97. *Phaeo-*Chl* *cl** (Chl *cs*)

98. *Phaeo-*Chl* *cm** (Chl *ct*)

99. *Phaeo-*Chl* *cn** (Chl *cu*)

100. *Phaeo-*Chl* *co** (Chl *cv*)

101. *Phaeo-*Chl* *cp** (Chl <

11

[illegible]

00 3401
 17 30 3501
 18 30 3601
 19 30 3701
 20 30 3801
 21 30 3901
 22 30 4001
 23 30 4101
 24 30 4201
 25 30 4301
 26 30 4401
 27 30 4501
 28 30 4601
 29 30 4701
 30 30 4801
 31 30 4901
 32 30 5001
 33 30 5101
 34 30 5201
 35 30 5301
 36 30 5401
 37 30 5501
 38 30 5601
 39 30 5701
 40 30 5801
 41 30 5901
 42 30 6001
 43 30 6101
 44 30 6201
 45 30 6301
 46 30 6401
 47 30 6501
 48 30 6601
 49 30 6701
 50 30 6801
 51 30 6901
 52 30 7001
 53 30 7101
 54 30 7201
 55 30 7301
 56 30 7401
 57 30 7501
 58 30 7601
 59 30 7701
 60 30 7801
 61 30 7901
 62 30 8001
 63 30 8101
 64 30 8201
 65 30 8301
 66 30 8401
 67 30 8501
 68 30 8601
 69 30 8701
 70 30 8801
 71 30 8901
 72 30 9001

PEAK OUTFLOW IS 383. AT TIME 44.00 HOURS

•DVP•

```

INFLOW(I), OUTFLOW(I) AND OBSERVED FLOW(*)
      4.
      STATION 1
      1000
      800
      600

```

0	1	2	3	4	5	6	7	8	9	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z
00	01	02	03	04	05	06	07	08	09	0A	0B	0C	0D	0E	0F	0G	0H	0I	0J	0K	0L	0M	0N	0O	0P	0Q	0R	0S	0T	0U	0V	0W	0X	0Y	0Z

FLAHERTY GIAVARA ASSOCIATES, P. C.

[illegible]



STATION 1, PLAN 1, RATIO 8
END-OF-PERIOD HYDROGRAPH ORDINATES

OUTFLOW

41.	46.	53.	64.	81.	109.	122.	218.	303.	416.
578	826	1181	1495	1725	1930	1850	1742	1662	1494
313	1339	1967	2820	3706	4630	5532	5909	6625	7428
977	2594	3957	5323	6705	8088	9471	10577	12433	14966
297	754	1150	1522	1883	2238	2597	2916	3293	3746
160	406	617	823	1025	1225	1421	160	193	226

STORAGE

[illegible]

PEAK OUTFLOW IS 1860. AT TIME 43.30 HOURS

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL	VOLUME
1860	1441	587	240	28834	816
53	41	17	7		10.02
	6.01	9.80	25.52		259.59
	157.71	278.85	1115.1		25191
	7.15	11.63	1470		1470
	882	1437			

ONE

GRATIAN

INFLOW(I), OUTFLOW(O) AND OBSERVED FLOW(F)

Time	Inflow (I)	Outflow (O)	Observed Flow (F)
0	1000	0	0
5	1000	1500	1500
10	2000	2200	2200
15	2000	2500	2500
20	3000	2400	2400
25	3000	2200	2200
30	3000	2000	2000
35	3000	1800	1800
40	3000	1600	1600
45	3000	1500	1500
50	3000	1500	1500

5 00 101
 6 00 111
 7 00 121
 8 00 131
 9 00 141
 10 00 151
 11 00 161
 12 00 171
 13 00 181
 14 00 191
 15 00 201
 16 00 211
 17 00 221
 18 00 231
 19 00 241
 20 00 251
 21 00 261
 22 00 271
 23 00 281
 24 00 291
 25 00 301
 26 00 311
 27 00 321
 28 00 331
 29 00 341
 30 00 351
 31 00 361
 32 00 371
 33 00 381
 34 00 391
 35 00 401
 36 00 411
 37 00 421
 38 00 431
 39 00 441
 40 00 451
 41 00 461
 42 00 471
 43 00 481
 44 00 491
 45 00 501
 46 00 511
 47 00 521
 48 00 531
 49 00 541
 50 00 551
 51 00 561
 52 00 571
 53 00 581
 54 00 591
 55 00 601
 56 00 611
 57 00 621
 58 00 631
 59 00 641
 60 00 651
 61 00 661
 62 00 671
 63 00 681
 64 00 691
 65 00 701
 66 00 711
 67 00 721
 68 00 731
 69 00 741
 70 00 751
 71 00 761
 72 00 771
 73 00 781
 74 00 791
 75 00 801
 76 00 811
 77 00 821
 78 00 831
 79 00 841
 80 00 851
 81 00 861
 82 00 871
 83 00 881
 84 00 891
 85 00 901
 86 00 911
 87 00 921
 88 00 931
 89 00 941
 90 00 951
 91 00 961
 92 00 971
 93 00 981
 94 00 991
 95 00 1001
 96 00 1011
 97 00 1021
 98 00 1031
 99 00 1041
 100 00 1051
 101 00 1061
 102 00 1071
 103 00 1081
 104 00 1091
 105 00 1101
 106 00 1111
 107 00 1121
 108 00 1131
 109 00 1141
 110 00 1151
 111 00 1161
 112 00 1171
 113 00 1181
 114 00 1191
 115 00 1201
 116 00 1211
 117 00 1221
 118 00 1231
 119 00 1241
 120 00 1251
 121 00 1261
 122 00 1271
 123 00 1281
 124 00 1291
 125 00 1301
 126 00 1311
 127 00 1321
 128 00 1331
 129 00 1341
 130 00 1351
 131 00 1361
 132 00 1371
 133 00 1381
 134 00 1391
 135 00 1401
 136 00 1411
 137 00 1421
 138 00 1431
 139 00 1441
 140 00 1451
 141 00 1461
 142 00 1471
 143 00 1481
 144 00 1491
 145 00 1501
 146 00 1511
 147 00 1521
 148 00 1531
 149 00 1541
 150 00 1551
 151 00 1561
 152 00 1571
 153 00 1581
 154 00 1591
 155 00 1601
 156 00 1611
 157 00 1621
 158 00 1631
 159 00 1641
 160 00 1651
 161 00 1661
 162 00 1671
 163 00 1681
 164 00 1691
 165 00 1701
 166 00 1711
 167 00 1721
 168 00 1731
 169 00 1741
 170 00 1751
 171 00 1761
 172 00 1771
 173 00 1781
 174 00 1791
 175 00 1801
 176 00 1811
 177 00 1821
 178 00 1831
 179 00 1841
 180 00 1851
 181 00 1861
 182 00 1871
 183 00 1881
 184 00 1891
 185 00 1901
 186 00 1911
 187 00 1921
 188 00 1931
 189 00 1941
 190 00 1951
 191 00 1961
 192 00 1971
 193 00 1981
 194 00 1991
 195 00 2001
 196 00 2011
 197 00 2021
 198 00 2031
 199 00 2041
 200 00 2051
 201 00 2061
 202 00 2071
 203 00 2081
 204 00 2091
 205 00 2101
 206 00 2111
 207 00 2121
 208 00 2131
 209 00 2141
 210 00 2151
 211 00 2161
 212 00 2171
 213 00 2181
 214 00 2191
 215 00 2201
 216 00 2211
 217 00 2221
 218 00 2231
 219 00 2241
 220 00 2251
 221 00 2261
 222 00 2271
 223 00 2281
 224 00 2291
 225 00 2301
 226 00 2311
 227 00 2321
 228 00 2331
 229 00 2341
 230 00 2351
 231 00 2361
 232 00 2371
 233 00 2381
 234 00 2391
 235 00 2401
 236 00 2411
 237 00 2421
 238 00 2431
 239 00 2441
 240 00 2451
 241 00 2461
 242 00 2471
 243 00 2481
 244 00 2491
 245 00 2501
 246 00 2511
 247 00 2521
 248 00 2531
 249 00 2541
 250 00 2551
 251 00 2561
 252 00 2571
 253 00 2581
 254 00 2591
 255 00 2601
 256 00 2611
 257 00 2621
 258 00 2631
 259 00 2641
 260 00 2651
 261 00 2661
 262 00 2671
 263 00 2681
 264 00 2691
 265 00 2701
 266 00 2711
 267 00 2721
 268 00 2731
 269 00 2741
 270 00 2751
 271 00 2761
 272 00 2771
 273 00 2781
 274 00 2791
 275 00 2801
 276 00 2811
 277 00 2821
 278 00 2831
 279 00 2841
 280 00 2851
 281 00 2861
 282 00 2871
 283 00 2881
 284 00 2891
 285 00 2901
 286 00 2911
 287 00 2921
 288 00 2931
 289 00 2941
 290 00 2951
 291 00 2961
 292 00 2971
 293 00 2981
 294 00 2991
 295 00 3001
 296 00 3011
 297 00 3021
 298 00 3031
 299 00 3041
 300 00 3051
 301 00 3061
 302 00 3071
 303 00 3081
 304 00 3091
 305 00 3101
 306 00 3111
 307 00 3121
 308 00 3131
 309 00 3141
 310 00 3151
 311 00 3161
 312 00 3171
 313 00 3181
 314 00 3191
 315 00 3201
 316 00 3211
 317 00 3221
 318 00 3231
 319 00 3241
 320 00 3251
 321 00 3261
 322 00 3271
 323 00 3281
 324 00 3291
 325 00 3301
 326 00 3311
 327 00 3321
 328 00 3331
 329 00 3341
 330 00 3351
 331 00 3361
 332 00 3371
 333 00 3381
 334 00 3391
 335 00 3401
 336 00 3411
 337 00 3421
 338 00 3431
 339 00 3441
 340 00 3451
 341 00 3461
 342 00 3471
 343 00 3481
 344 00 3491
 345 00 3501
 346 00 3511
 347 00 3521
 348 00 3531
 349 00 3541
 350 00 3551
 351 00 3561
 352 00 3571
 353 00 3581
 354 00 3591
 355 00 3601
 356 00 3611
 357 00 3621
 358 00 3631
 359 00 3641
 360 00 3651
 361 00 3661
 362 00 3671
 363 00 3681
 364 00 3691
 365 00 3701
 366 00 3711
 367 00 3721
 368 00 3731
 369 00 3741
 370 00 3751
 371 00 3761
 372 00 3771
 373 00 3781
 374 00 3791
 375 00 3801
 376 00 3811
 377 00 3821
 378 00 3831
 379 00 3841
 380 00 3851
 381 00 3861
 382 00 3871
 383 00 3881
 384 00 3891
 385 00 3901
 386 00 3911
 387 00 3921
 388 00 3931
 389 00 3941
 390 00 3951
 391 00 3961
 392 00 3971
 393 00 3981
 394 00 3991
 395 00 4001
 396 00 4011
 397 00 4021
 398 00 4031
 399 00 4041
 400 00 4051
 401 00 4061
 402 00 4071
 403 00 4081
 404 00 4091
 405 00 4101
 406 00 4111
 407 00 4121
 408 00 4131
 409 00 4141
 410 00 4151
 411 00 4161
 412 00 4171
 413 00 4181
 414 00 4191
 415 00 4201
 416 00 4211
 417 00 4221
 418 00 4231
 419 00 4241
 420 00 4251
 421 00 4261
 422 00 4271
 423 00 4281
 424 00 4291
 425 00 4301
 426 00 4311
 427 00 4321
 428 00 4331
 429 00 4341
 430 00 4351
 431 00 4361
 432 00 4371
 433 00 4381
 434 00 4391
 435 00 4401
 436 00 4411
 437 00 4421
 438 00 4431
 439 00 4441
 440 00 4451
 441 00 4461
 442 00 4471
 443 00 4481
 444 00 4491
 445 00 4501
 446 00 4511
 447 00 4521
 448 00 4531
 449 00 4541
 450 00 4551
 451 00 4561
 452 00 4571
 453 00 4581
 454 00 4591
 455 00 4601
 456 00 4611
 457 00 4621
 458 00 4631
 459 00 4641
 460 00 4651
 461 00 4661
 462 00 4671
 463 00 4681
 464 00 4691
 465 00 4701
 466 00 4711
 467 00 4721
 468 00 4731
 469 00 4741
 470 00 4751
 471 00 4761
 472 00 4771
 473 00 4781
 474 00 4791
 475 00 4801
 476 00 4811
 477 00 4821
 478 00 4831
 479 00 4841
 480 00 4851
 481 00 4861
 482 00 4871
 483 00 4881
 484 00 4891
 485 00 4901
 486 00 4911
 487 00 4921
 488 00 4931
 489 00 4941
 490 00 4951
 491 00 4961
 492 00 4971
 493 00 4981
 494 00 4991
 495 00 5001
 496 00 5011
 497 00 5021
 498 00 5031
 499 00 5041
 500 00 5051
 501 00 5061
 502 00 5071
 503 00 5081
 504 00 5091
 505 00 5101
 506 00 5111
 507 00 5121
 508 00 5131
 509 00 5141
 510 00 5151
 511 00 5161
 512 00 5171
 513 00 5181
 514 00 5191
 515 00 5201
 516 00 5211
 517 00 5221
 518 00 5231
 519 00 5241
 520 00 5251
 521 00 5261
 522 00 5271
 523 00 5281
 524 00 5291
 525 00 5301
 526 00 5311
 527 00 5321
 528 00 5331
 529 00 5341
 530 00 5351
 531 00 5361
 532 00 5371
 533 00 5381
 534 00 5391
 535 00 5401
 536 00 5411
 537 00 5421
 538 00 5431
 539 00 5441
 540 00 5451
 541 00 5461
 542 00 5471
 543 00 5481
 544 00 5491
 545 00 5501
 546 00 5511
 547 00 5521
 548 00 5531
 549 00 5541
 550 00 5551
 551 00 5561
 552 00 5571
 553 00 5581
 554 00 5591
 555 00 5601
 556 00 5611
 557 00 5621
 558 00 5631
 559 00 5641
 560 00 5651
 561 00 5661
 562 00 5671
 563 00 5681
 564 00 5691
 565 00 5701
 566 00 5711
 567 00 5721
 568 00 5731
 569 00 5741
 570 00 5751
 571 00 5761
 572 00 5771
 573 00 5781
 574 00 5791
 575 00 5801
 576 00 5811
 577 00 5821
 578 00 5831
 579 00 5841
 580 00 5851
 581 00 5861
 582 00 5871
 583 00 5881
 584 00 5891
 585 00 5901
 586 00 5911
 587 00 5921
 588 00 5931
 589 00 5941
 590 00 5951
 591 00 5961
 592 00 5971
 593 00 5981
 594 00 5991
 595 00 6001
 596 00 6011
 597 00 6021
 598 00 6031
 599 00 6041
 600 00 6051
 601 00 6061
 602 00 6071
 603 00 6081
 604 00 6091
 605 00 6101
 606 00 6111
 607 00 6121
 608 00 6131
 609 00 6141
 610 00 6151
 611 00 6161
 612 00 6171
 613 00 6181
 614 00 6191
 615 00 6201
 616 00 6211
 617 00 6221
 618 00 6231
 619 00 6241
 620 00 6251
 621 00 6261
 622 00 6271
 623 00 6281
 624 00 6291
 625 00 6301
 626 00 6311
 627 00 6321
 628 00 6331
 629 00 6341
 630 00 6351
 631 00 6361
 632 00 6371
 633 00 6381
 634 00 6391
 635 00 6401
 636 00 6411
 637 00 6421
 638 00 6431
 639 00 6441
 640 00 6451
 641 00 6461
 642 00 6471
 643 00 6481
 644 00 6491
 645 00 6501
 646 00 6511
 647 00 6521
 648 00 6531
 649 00 6541
 650 00 6551
 651 00 6561
 652 00 6571
 653 00 6581
 654 00 6591
 655 00 6601
 656 00 6611
 657 00 6621
 658 00 6631
 659 00 6641
 660 00 6651
 661 00 6661
 662 00 6671
 663 00 6681
 664 00 6691
 665 00 6701
 666 00 6711
 667 00 6721
 668 00 6731
 669 00 6741
 670 00 6751
 671 00 6761
 672 00 6771
 673 00 6781
 674 00 6791
 675 00 6801
 676 00 6811
 677 00 6821
 678 00 6831
 679 00 6841
 680 00 6851
 681 00 6861
 682 00 6871
 683 00 6881
 684 00 6891
 685 00 6901
 686 00 6911
 687 00 6921
 688 00 6931
 689 00 6941
 690 00 6951
 691 00 6961
 692 00 6971
 693 00 6981
 694 00 6991
 695 00 7001
 696 00 7011
 697 00 7021
 698 00 7031
 699 00 7041
 700 00 7051
 701 00 7061
 702 00 7071
 703 00 7081
 704 00 7091
 705 00 7101
 706 00 7111
 707 00 7121
 708 00 7131
 709 00 7141
 710 00 7151
 711 00 7161
 712 00 7171
 713 00 7181
 714 00 7191
 715 00 7201
 716 00 7211
 717 00 7221
 718 00 7231
 719 00 7241
 720 00 7251
 721 00 7261
 722 00 7271
 723 00 7281
 724 00 7291
 725 00 7301
 726 00 7311
 727 00 7321
 728 00 7331
 729 00 7341
 730 00 7351
 731 00 7361
 732 00 7371
 733 00 7381
 734 00 7391
 735 00 7401
 736 00 7411
 737 00 7421
 738 00 7431
 739 00 7441
 740 00 7451
 741 00 7461
 742 00 7471
 743 00 7481
 744 00 7491
 745 00 7501
 746 00 7511
 747 00 7521
 748 00 7531
 749 00 7541
 750 00 7551
 751 00 7561
 752 00 7571
 753 00 7581
 754 00 7591
 755 00 7601
 756 00 7611
 757 00 7621
 758 00 7631
 759 00 7641
 760 00 7651
 761 00 7661
 762 00 7671
 763 00 7681
 764 00 7691
 765 00 7701
 766 00 7711
 767 00 7721
 768 00 7731
 769 00 7741
 770 00 7751
 771 00 7761
 772 00 7771
 773 00 7781
 774 00 7791
 775 00 7801
 776 00 7811
 777 00 7821
 778 00 7831
 779 00 7841
 780 00 7851
 781 00 7861
 782 00 7871

PAGE 0035

STYLING

STATION 1, PLAN 1, RATIO 9
 END-OF-PERIOD HYDROGRAPH ORDINATES

0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100

PEAK OUTFLOW IS 3852 AT TIME 43.00 HOURS

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL
3852	3037	1193	489	5862
107	86	19.91	20.37	1861
	12.58	505.76	517.76	2424
	321.77	2367	2990	2990
	1507	2920		
	1859			

STATION 1

AD-A109 974

FLAHERTY-GIAVARA ASSOCIATES NEW HAVEN CT
NATIONAL DAM SAFETY PROGRAM. GUILFORD LAKE DAM (INVENTORY NUMBE--ETC(U)
SEP 81 H C FLAHERTY

F/G 13/13

DACW51-81-C-0006


NL

UNCLASSIFIED

2-2
100-10



END
DATA
FILMED
82
DTIC



INFLOW(I), OUTFLOW(O) AND OBSERVED FLOW(*)

0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99
0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99
0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99

FLAHERTY GIAVARA ASSOCIATES, P. C.

[illegible]

7. 00114. 10
 9. 00115. 10
 10. 00116. 10
 11. 00117. 10
 12. 00118. 10
 13. 00119. 10
 14. 00120. 10

OVN

PEAK FLOW AND STORAGE (END OF PERIOD) SUMMARY FOR MULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS
 FLOWS IN CUBIC FEET PER SECOND (CUBIC METERS PER SECOND)
 AREA IN SQUARE MILES (SQUARE KILOMETERS)

OPERATION	STATION	AREA	PLAN	RATIO 1	RATIO 2	RATIO 3	RATIO 4	RATIO 5	RATIO 6	RATIO 7	RATIO 8	RATIO 9
HYDROGRAPH AT	1	2.23	1	13.67	20.53	21.90	23.26	24.63	26.00	27.37	28.74	30.11
ROUTED TO	1	2.23	1	249	407	440	473	510	545	583	620	657
		5.78		7.06	11.52	12.45	13.45	14.44	15.45	16.50	17.55	18.60

SUMMARY OF DAM SAFETY ANALYSIS

PLAN	ELEVATION	INITIAL VALUE	SPILLWAY CREST	TOP OF DAM
1	1558.00	1558.00	1558.00	1560.20
	0.00	0.00	0.00	174.00
				442.00

RATIO OF FLOW	MAXIMUM RESERVOIR W.S. ELEV.	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
0.10	1559.51	0.00	114	249	0.00	44.50	0.00
0.15	1560.08	0.00	173	407	0.00	44.00	0.00
0.20	1560.70	0.00	182	440	0.00	44.00	0.00
0.25	1561.40	0.00	191	473	2.00	44.00	0.00
0.30	1562.10	0.00	199	510	3.50	44.00	0.00
0.35	1562.80	0.00	208	545	4.00	44.00	0.00
0.40	1563.50	0.00	214	583	4.50	43.50	0.00
0.45	1564.20	0.00	221	620	5.00	43.00	0.00
0.50	1564.90	0.00	228	657	5.50	43.00	0.00
0.55	1565.60	0.00	235	694	6.00	43.00	0.00
0.60	1566.30	0.00	242	731	6.50	43.00	0.00
0.65	1567.00	0.00	249	768	7.00	43.00	0.00
0.70	1567.70	0.00	256	805	7.50	43.00	0.00
0.75	1568.40	0.00	263	842	8.00	43.00	0.00
0.80	1569.10	0.00	270	879	8.50	43.00	0.00
0.85	1569.80	0.00	277	916	9.00	43.00	0.00
0.90	1570.50	0.00	284	953	9.50	43.00	0.00
0.95	1571.20	0.00	291	990	10.00	43.00	0.00
1.00	1571.90	0.00	298	1027	10.50	43.00	0.00

 FLOOD HYDROGRAPH PACKAGE (HEC-1)
 DAM SAFETY VERIFICATION JULY 1978
 LAST MODIFICATION 26 FEB 79

FLAHERTY DIAVARA ASSOCIATES, P. C.

PAGE 0040

APPENDIX D

PREVIOUS INSPECTION REPORTS/AVAILABLE DOCUMENTS

PREVIOUS REPORTS

GUILFORD WATER SYSTEM ENGINEERING REPORT

GENERAL AND HISTORICAL

Available history relative to the age of the Guilford Water System and past performance is incomplete due to an absence of records kept under private ownership.

The system presently servicing the Hamlet of Guilford was purchased in 1961 by the Emerson's Water Works Company, Inc. from the Guilford Water Works Company, Inc. A search of the deeds indicates the system to be existant in 1890 and for an indeterminate period prior to that date.

Water is presently furnished to two churches, one post office, one firehouse, one school garage, two stores, one restaurant, two farms, and 83 residential consumers. An additional annual charge is levied against the Guilford Fire District.

SOURCE OF SUPPLY

The Emerson's Water Works Company owns the right to flood lands now under Guilford Lake to a depth of 15 feet from the bed rock bottom. A stone dam with a 6-inch concrete cap now exists at the southerly end of Guilford Lake presumably at the location described in the original deeds, some of which date to 1827. An earth fill extending for a considerable distance behind (on the lake side) of the dam could possibly be the result of a century of natural sedimentation as the entire concrete cap of the dam also serves as the spillway. This earth fill strengthens the dam and increases resistance to water penetration. Inspections indicate the structure to be relatively watertight, to require moderate repairs to the stonework, and to require a complete replacement of the concrete cap for one half of its length across the dam. An application to the Corps of Engineers for a more complete examination of the structure is recommended. This report includes a cursory examination of the condition of the dam as can be determined by visual observations under the condition of water flowing over the top of the dam. A detailed survey and report should be made in the immediate future to ensure the structural stability and safety of the dam.

Guilford Lake is located approximately 0.4 miles from the Hamlet of Guilford, has a surface area of approximately 66 acres and a drainage area of approximately 2.2 square miles. The depth of the lake varies from five feet along the general shore line to 65 feet in the center; the relatively deep center resulting from flooding the portion of the lake existing prior to the construction of the dam with an additional 15 feet of water. A total dependable yield of 1.61 MGD

has been established in the Chenango County Comprehensive Water Report prepared in 1968 by the Engineering Firm of Metcalf and Eddy and approved by the State of New York. A copy of Fig. 12 titled Guilford Population Center Water Supply Requirements, included in this report, indicates a potential average daily demand of 60,000 gallons per day and a potential maximum daily demand of 130,000 gpd in the year 2020 for the Hamlet of Guilford, both of which are considerably less than the total dependable yield. The comprehensive report recommends continuing the utilization of Guilford Lake as the source of water supply.

OTHER PROPERTIES

Lands owned by the water company include a portion of lands under the surface of Guilford Lake extending from the dam site northerly to the surface of the original lake prior to construction of the dam. Other lands include the stream bed and the major portion of the bank southerly to properties of James Brown.

The rights titles, and interest in and to the water pipes within the existing system; the rights, title, and interest in and to all contracts for supplying and conveying water within the Town of Guilford; and the rights to lay, repair, and continue the water system are also owned by the present water company.

QUALITY OF WATER

Raw water from Guilford Lake is presently used by the consumers with no pre-treatment other than chlorination. Previous tests on raw water samples have been recorded as follows:

Iron	0.38 (relatively high)
Manganese	0.38 (relatively high)
Color	22 Turbidity 3 ppm, Odor--Earthy
Hardness	35 ppm (good)
P. H.	7.1 Silica 3.0 ppm

Bacteriological examinations indicate a moderate count in the raw water supplies during the early part of the year which gradually increases during the summer months to the point where the water is not acceptable for a community water supply.

Periodic samples taken with the distribution system after chlorination have been accepted as satisfactory for potable water.

The water supply is generally satisfactory for consumption if chlorinated. Consideration should be given to removals of iron and manganese and to improvement of turbidity and odor.

WATER MAINS AND SERVICES

The existing water distribution system includes 2880 feet of 6 inch cast iron pipe, 5068 feet of 4 inch cast iron pipe and 200 feet

Town of Guilford

R. D. 1 - Box 103
Guilford, N. Y. 13780

March 23, 1981

Dear Sir:


Re: your recent inspection of Guilford Lake Dam.

I have checked and found there were no blueprints on the recent refacing job done on the dam; not so unusual the way other practices have been carried out during the last 8 years in the Town.

I have found that 3/4 inch steel reinforcing rods were used in a horizontal and vertical pattern extending from bed rock to and including the top and for the wing walls.


The face concrete was 8 to 10 inches wide and the top had 6 inches. Both wing walls are new. We feel with the gravel build up behind the dam and the very constant flow of water at all times this structure will be very sound for many years.

Sincerely



Clifford E. Wade
Supervisor

APPENDIX E
STRUCTURAL STABILITY ANALYSIS



Composite action - Stone (water jet compacted) + Conc.

$$\frac{\text{Section}}{12' \times 16' \times .1} = \frac{\text{Wt.}}{19.2 \text{ K}}$$

Coef. of frict. = 1.0 $P_{\text{Resist.}} = 19.2 \text{ K/Ft}$
 $U = \frac{2}{3} (17') \times .0624 \times \frac{12'}{2} = 4.24 \text{ K}$

P_{Active} :

(1) Ht. of water 1' above Spillway

(2) Ice at Top of Spillway

(3) .5 PMF Ht. of water at 4.8' above Spillway

Loading Case I:

$$P_w = 1' \times .0624 = .0624 \text{ K/Ft} \times 16' = 1 \text{ K} \quad (1) @ \frac{16}{2} =$$

$$P_{ss} = .055 \times \frac{16^2}{2} = 7.04 \text{ K} @ \frac{16}{3}$$

F.S.O.T.: Insufficient data

$$\text{F.S.S.L.: } \frac{19.2 \times 4.24}{8.04} = 1.86 \text{ OK}$$

Loc. of Res.: N/A



Load'g Case: Normal + Ice

$$P_w = 1^k/ft$$

$$P_{ice} = 5^k/ft$$

$$P_{ss} = 7.04^k/ft$$

$$F.S.O.T. = N/A$$

$$Loc. of Res. = N/A$$

$$F.S.SL. = \frac{19.2 - 4.24}{13.04} = 1.15 \text{ Undesirable}$$

Load'g Case: .5 PMF

$$P_w = 4.8 \times .0624 \times 16 = 4.79^k/ft$$

$$P_{ss} = 7.04^k/ft$$

$$U = 4.24^k$$

$$F.S.O.T. = N/A \quad Loc. of Res. = N/A$$

$$F.S.SL. = \frac{19.2 - 4.24}{11.83} = 1.26 \text{ Undesirable}$$

Max. Oper. Cond.

Ht. of water level

2.2' above Spillway

$$P_w = 2.2 \times .0624 \times 16 = 2.2^k$$

$$P_{ss} = 7.04^k$$

$$U = 4.24^k \uparrow$$

$$F.S.O.T. = N/A \quad Loc. of Res. = N/A$$

$$F.S.SL. = \frac{19.2 - 4.24}{9.24} = 1.62 \text{ OK}$$

APPENDIX F

REFERENCES

REFERENCES


1. Chow, Ven Te, Editor - Handbook of Applied Hydrology. McGraw-Hill Book Company, New York, New York, 1964.
2. Hydrologic Engineering Center, U.S. Army Corps of Engineers, HEC-1 Flood Hydrograph Package, Users Manual. Davis, California, January 1973.
3. Hydrologic Engineering Center, U.S. Army Corps of Engineers, Flood Hydrograph Package (HEC-1), Users Manual for Dam Safety Investigations, Davis, California, September 1978.
4. King, Horace and Brater, Ernest. Handbook of Hydraulics, 5th Edition. McGraw-Hill Book Company, New York, New York, 1963.
5. Riedel, J.T., Appleby, J.F. and Schloemer, R.W. Seasonal Variation of the Probable Maximum Precipitation East of the 105th Meridian for Areas from 10 to 1000 Square Miles and Durations of 6, 12, 24, and 48 Hours (Hydrometeorological Report No. 33) U.S. Department of Commerce - Weather Bureau and U.S. Department of the Army - Corps of Engineers, Washington, D.C., April 1956
6. U.S. Department of the Interior, Bureau of Reclamation, Design of Small Dams, Second Edition, Washington, D.C., 1973.

APPENDIX G

DRAWINGS

NAME OF DAM :

FED. ID NO. : 1483



SECTION THRU CONC. DAM & SPILLWAY.

FILMED
3-8